

Memorandum



To: Planning Commission

From: Christopher Solberg, City Planner

Date: 5/14/2015

Re: Public Hearing regarding text amendments to Sections 2.02, 5.05, 5.10, and 5.11 in regards to Animal Specialty Services, Pet Shops, and Kennels

Attached to this memo are several revisions to the amendments which were heard by the Planning Commission at the public hearing on March 19, 2015. At that time the Commission recommended approval and the amendments were forwarded to the City Council.

At their public hearing on April 29, 2015, the City Council voted to make several other amendments, including:

- “Animal Specialty Services” should be changed from a Permitted Use to a Permitted **Conditional** Use within the C-1 and C-2 districts.
- “Pet Shops”, a use which has been listed as a Permitted Use, should also be changed to a Permitted **Conditional** Use within the C-1 and C-2 districts.

Because the amendment to the “Pet Shops” use proposed by the City Council had not been the subject of the public hearing by the Planning Commission, a new public hearing has been advertised for consideration of this change.

Staff has also revised the definition for “Animal Specialty Services” to include overnight boarding as part of this use. Along with this change, staff has reorganized the layout of the definitions section of the Zoning Ordinance into sections, separated by letters of the alphabet, to simplify future amendments to this section.

While preparing these amendments, staff noticed the intent statement of the C-1 District (subsection 5.10.01) is outdated and confusing. This statement has been rewritten to better reflect the purpose of the district.

As was the case in the previous amendments heard by the Planning Commission, staff is also recommending the removal of kennels as an allowed use in the TA Transitional Agriculture district.

STAFF RECOMMENDATION: Staff recommends approval.

Section 5.05 TA Transitional Agriculture District

5.05.01 Intent: The Transitional Agriculture District is established to recognize these properties as agricultural at present with the understanding that they may be suitable for development in the future. This district allows for existing agricultural properties to continue using the land in that manner.

5.05.02 Permitted Uses.

- 5.05.02.01 Farming, pasturing, truck gardening, orchards, greenhouses and nurseries, including the sale of products raised on the premises, provided that no livestock feedlot or yard for more than twelve (12) animals shall be established.
- 5.05.02.02 Farm dwellings for the owners and their families, tenants, and employees.
- 5.05.02.03 Public parks and recreation areas, playgrounds and conservation areas including flood control facilities.
- 5.05.02.04 Railroads, not including switching, terminal facilities or freight yards.
- 5.05.02.05 Public overhead and underground local distribution utilities.
- 5.05.02.06 Single family dwelling.
- 5.05.02.07 Churches.
- 5.05.02.08 Hydrogenation process.
- 5.05.02.09 Public services.
- 5.05.02.10 Publicly owned and operated facilities.
- 5.05.02.11 Roadside stands offering for sale agriculture products on the premises.

5.05.03 Permitted Conditional Uses:

- 5.05.03.01 Radio, television and wireless communication towers and transmitters, as per Section 7.11.
- 5.05.03.02 Cemeteries, provided all structures are located at least one hundred (100) feet from all property lines.
- 5.05.03.03 Wastewater treatment facilities.
- 5.05.03.04 Private recreation areas and facilities including country clubs, golf courses (but not miniature golf), and swimming pools.
- 5.05.03.05 Home occupations, as per Section 7.10.
- 5.05.03.06 Raising and care of animals for 4-H, Future Farmer of America (FFA) or other rural/school organizations.
- 5.05.03.07 Wind energy systems on tracts of more than ten (10) acres, as per Section 7.18.
- 5.05.03.09 Airports.
- 5.05.03.10 Campgrounds.
- 5.05.03.12 **Kennels and stables.**
- 5.05.03.13 Water reservoir.

5.05.04 Permitted Accessory Uses:

- 5.05.04.01 Buildings and uses customarily incidental to the permitted and conditional uses.
- 5.05.04.02 Temporary buildings incidental to construction work where such buildings or structures are removed upon completion of work.
- 5.05.04.03 Signs as provided for in Section 7.01 through 7.04.
- 5.05.04.04 Parking as provided for in Section 7.05 through 7.09.
- 5.05.04.05 Private swimming pool, tennis court and other similar facilities in conjunction with a residence.
- 5.05.04.06 Storage or parking of vehicles, boats, campers and trailer, as per Section 7.13.

5.05.05 Height and Lot Requirements:

- 5.05.05.01 The height and minimum lot requirements shall be as follows:

Uses	Lot Area (Acres)	Lot Width	Front Yard	Side Yard	Rear Yard	Max. Height	Max. Lot Coverage
Residential Dwelling	20	660'	75'	25'	25'	35'	-
Other Permitted Uses	20	660'	75'	25'	25'	45'	-
Other Permitted Conditional Uses	20	660'	75'	25'	25'	45'	-
Accessory Buildings	-	-	100'	25'	10'	17'	-

Section 5.10 C-1 Shopping Center Commercial.

5.10.01 Intent: ~~The purpose and intent of the City of La Vista in establishing the C-1 Shopping Center Commercial District is to provide convenient local retail shopping and service areas within the city for all residents and to provide for the development of new local commercial districts where so designated. This includes uses such as retail stores, banks, theaters, business offices, restaurants, and taverns. This district adds certain design standards in comparison to zoning districts located along 84th Street and at the intersection of 96th and Giles Road. They are designed to promote:~~

~~5.10.01.01 Safe traffic circulation on and off and across the highway.~~

~~5.10.01.02 A high quality of design and site planning.~~

~~5.10.01.03 Flexibility in development in order to provide an attractive, viable employment corridor.~~

Formatted: Font: 10 pt

Formatted: Indent: Hanging: 0.5", Tab stops: -1", Left + -0.5", Left

Formatted: Indent: Left: 0", Hanging: 0.5", Tab stops: -1", Left + -0.5", Left

This district prohibits all exterior storage by a primary use unless a separate Conditional Use Permit is requested for the use and granted by the City.

5.10.02 Permitted uses:

5.10.02.01 *Medical/dental offices and business services including: attorneys, banks, insurance, real estate offices, postal stations, credit services, security brokers, dealers and exchange, title abstracting, finance services and investment services; but not including uses defined in Adult Establishment. (Ordinance No. 950, 3-1-05)*

5.10.02.02 Child care center.

5.10.02.03 Dance studio, not including uses defined in Adult Establishment.

5.10.02.04 Meeting hall, not including uses defined in Adult Establishment.

5.10.02.05 Museum, art gallery.

5.10.02.06 Retail business or service establishment supplying commodities or performing services, such as, or in compatibility with and including the following:

1. Apparel shop.
2. Appliance store.
3. Antique store.
4. Automobile parts and supply store.
5. Bakery shop (retail).
6. Barber and Beauty shop.
7. Bicycle shop.
8. Book store, not including uses defined in Adult Establishment.
9. Brew-on premises store.
10. Camera store.
11. Communication services.
12. Computer store.
13. Confectionery.
14. Dairy products sales.
15. Drug store.
16. Dry cleaning and laundry pickup.
17. Exercise, fitness and tanning spa, not including uses defined in Adult Establishment.
18. Food Sales (Limited).
19. Food Sales (General).
20. Floral shop.
21. Mortuary.
22. Furniture store or showroom.
23. Gift and curio shop.
24. Gunsmith.
25. Hardware store.
26. Hobby, craft, toy store.
27. Jewelry store.
28. Liquor store.
29. Locksmith.

- 30. Meat market, retail.
- 31. Music retail store.
- 32. Newsstands, not including uses defined in Adult Establishment.
- 33. Paint store.
- 34. **Pet shop.**
- 35. Photographer.
- 36. Picture framing shop.
- 37. Reservation center.
- 38. Restaurants, cafes and fast food establishments.
- 39. Second hand stores.
- 40. Shoe store.
- 41. Sporting goods.
- 42. Stamp and coin stores.
- 43. Tailors and dressmakers.
- 44. Tanning salon.
- 45. Travel agencies.
- 46. Video store, not including uses defined in Adult Establishment.
- 47. Social club and fraternal organizations, not including uses defined in Adult Establishment.
- 48. Telephone exchange.
- 49. Telephone answering service.
- 50. Public overhead and underground local distribution utilities.
- 51. *Publicly owned and operated facilities. (Ordinance No. 950, 3-1-05)*

Formatted: Indent: 2", No bullets or numbering

5.10.03 Permitted Conditional Uses:

- 5.10.03.01 Recreational establishments.
- 5.10.03.02 Department Store.
- 5.10.03.03 Variety store, not including uses defined in Adult Establishment.
- 5.10.03.04 Amusement arcades.
- 5.10.03.05 Brew Pubs.
- 5.10.03.06 Coffee Kiosks.
- 5.10.03.07 Micro breweries when in conjunction with a restaurant.
- 5.10.03.08 Automated Teller Machines when not within the interior of a primary use.
- 5.10.03.09 Theater, indoor, not including uses defined in Adult Establishment.
- 5.10.03.10 Bowling center.
- 5.10.03.11 Business or trade school.
- 5.10.03.12 Commercial greenhouse.
- 5.10.03.13 Mail order services.
- 5.10.03.14 Pinball or video games business.
- 5.10.03.15 Tavern and cocktail lounge, not including uses defined in Adult Establishment.
- 5.10.03.16 Totally enclosed, automated and conveyor-style car washes.
- 5.10.03.17 Convenience store with limited fuel sales.
- 5.10.03.18 Garden supply and retail garden center.
- 5.10.03.19 Outdoor storage in conjunction with another primary use.
- 5.10.03.20 Pet Health Services, provided the following:
 - 1. Said use is totally enclosed within a building.
 - 2. Said services shall be provided for dogs, cats, birds, fish, and similar small animals customarily used as household pets.
 - 3. Typical uses include animal veterinary clinics with overnight boarding, only if medically necessary, not exceeding 48 hours.
 - 4. Grooming shall only be associated with medical appointment.
 - 5. This excludes uses for livestock and other large animals and uses for general grooming, dog bathing and clipping salons.
- 5.10.03.21 *Self-storage units, provided:*
 - 1. *Storage unit is an extension of an existing self-storage unit or facility.*

2. *The topography and access of the property will limit the development of identified commercial uses.*
3. *No outdoor storage.*
4. *Unit or facility provides perimeter fencing in accordance with this ordinance and a vegetative screen of at least six (6) feet in height and twenty (20) feet in width to any adjacent residential zoned property.*
5. *Lighting on site shall not be directed at or allowed to shine on any residential zoned property.*
6. *Applications for self-storage units under the terms of this Section shall be accompanied by evidence concerning the feasibility of the proposed request and its affect on surrounding property and shall include a site plan defining the areas to be developed with buildings and/or structures, the areas to be developed for parking, driveways and points of ingress and egress, the location and height of walls and fences, the location and type of landscaping, and the location, size and number of signs.*
7. *Such use shall not be located adjacent to the intersection of two or more arterial streets.*
8. *The property shall have at least one boundary line that is adjacent to other property that is zoned I-1 Light Industrial or I-2 Heavy Industrial.*
9. *Such use shall not include storage of explosives or hazardous materials and shall be in accordance with the intent, purpose and spirit of this ordinance and the Comprehensive Development Plan of La Vista, Nebraska.*

(Ordinance No. 954, 7-5-05)

5.10.03.22

Event center, provided:

1. *A conditional use permit would need to include specifics to the design and operation of the proposed center and individual activities, including, but not limited to, a detailed site plan and floor plan, a complete list of appointed or designated managers for each event at the center, and a complete description and duration of each event submitted to the city prior to each event.*
2. *Lighting on site shall not be directed at or allowed to shine on any residential zoned property.*
3. *Buildings utilized as event centers shall be accompanied by evidence concerning the feasibility of the proposed request and its affect on surrounding property and shall include a site plan defining the areas to be developed with buildings and/or structures, the areas to be developed for parking, driveways and points of ingress and egress, the location and height of walls and fences, the location and type of landscaping, and the location, size and number of signs.*
4. *All signage shall comply with the City's established regulations.*

(Ordinance No. 955, 7-19-05)

5.10.03.23

Animal Specialty Services with or without overnight boarding of animals and outdoor exercise areas.

← **Formatted:** Indent: Left: 0.5", Hanging: 1"

5.10.03.235, 10.03.24 Pet shop.

→ **Formatted:** Font: Italic

5.10.04 Permitted Accessory Uses:

- 5.10.04.01 Buildings and uses customarily incidental to the permitted uses.
- 5.10.04.02 Parking as allowed in Section 7.05 through 7.09.
- 5.10.04.03 Signs allowed in Section 7.01 through 7.04.
- 5.10.04.04 Landscaping as required by Section 7.17.

5.10.05 Permitted Temporary Uses

Temporary Uses require a permit from the City of La Vista and shall be valid only for a specific amount of time as indicated on said permit. *All platted lots or tracts of land may have a maximum number of four (4) temporary uses per calendar year. Such uses shall not last more than two (2) weeks per use, except as provided for hereafter. (Ordinance No. 998, 7-18-06)*

- 5.10.05.01 Temporary greenhouses.
- 5.10.05.02 Temporary structures as needed for sidewalk and other outdoor sales events.

- 5.10.05.03 Fireworks stands, provided the criteria are met as established by the City through separate Ordinances.
- 5.10.05.04 Buildings and uses incidental to construction work *are permitted to remain until completion or abandonment of the construction work, at which time they shall be removed. (Ordinance No. 998, 7-18-06)*
- 5.10.05.05 Temporary structure for festivals or commercial events.

5.10.06 Height and Lot Requirements:

- 5.10.06.01 The height and minimum lot requirements shall be as follows:

<i>Uses</i>	Lot Area (SF)	Lot Width	Front Yard	Side Yard	Rear Yard	Max. Height	Max. Lot Coverage
Permitted Uses	-	150'	25' ¹	10'	25'	45'	60%
Permitted Conditional Uses	-	150'	25' ¹	10'	25'	45'	60%

¹. 25' front yard setback required only when no parking is present in the front yard. If parking is located in the front yard then front yard setback is a minimum of fifty (50) feet.

5.10.07 Use Limitations:

- 5.10.07.01 When adjacent to residentially zoned land, no parking, drives or signs shall be allowed in any required yard within fifteen (15) feet of such district.
- 5.10.07.02 Furthermore, permanent screening shall be provided in this area in order to minimize impacts on residentially zoned property, as per Section 7.17.04.
- 5.10.07.03 Exterior lighting fixtures shall be shaded so that no direct light is cast upon any residential property and so that no glare is visible to any traffic on any public street.

Section 5.11 C-2 General Commercial District

5.11.01 Intent: The General Commercial District is intended to establish standards that will foster and maintain an area within the district boundaries that will benefit the retail trade, business, cultural, and social activities of the entire community. In addition, this district prohibits all exterior storage by a primary use unless a separate Conditional Use Permit is requested for the use and granted by the City.

5.11.02 Permitted Uses:

- 5.11.02.01 *Medical/dental offices and business services including: attorneys, banks, insurance, real estate offices, postal stations, printing, credit services, security brokers, dealers and exchange, title abstracting, finance services and investment services; but not including uses defined in Adult Establishment. (Ordinance No. 950, 3-1-05)*
- 5.11.02.02 Child care center.
- 5.11.02.03 Dance studio, not including uses defined in Adult Establishment.
- 5.11.02.04 Meeting hall, not including uses defined in Adult Establishment.
- 5.11.02.05 Museum, art gallery.
- 5.11.02.06 Retail business or service establishment supplying commodities or performing services, such as, or in compatibility with and including the following:
 - 1. Apparel shop.
 - 2. Appliance store.
 - 3. Antique store.
 - 4. Automobile parts and supply store.
 - 5. Bakery shop (retail).
 - 6. Barber and Beauty shop.
 - 7. Bicycle shop.
 - 8. Book store, not including uses defined in Adult Establishment.
 - 9. Brew-on premises store.
 - 10. Camera store.
 - 11. Communication services.
 - 12. Computer store.
 - 13. Confectionery.
 - 14. Dairy products sales.
 - 15. Drug store.
 - 16. Dry cleaning and laundry pickup.
 - 17. Exercise, fitness and tanning spa, not including uses defined in Adult Establishment.
 - 18. Floral shop.
 - 19. Mortuary.
 - 20. Food Sales (Limited).
 - 21. Food Sales (General).
 - 22. Furniture store or showroom.
 - 23. Gift and curio shop.
 - 24. Gunsmith.
 - 25. Hardware store.
 - 26. Hobby, craft, toy store.
 - 27. Jewelry store.
 - 28. Liquor store.
 - 29. Locksmith.
 - 30. Meat market, retail.
 - 31. Music retail store.
 - 32. Music studio.
 - 33. Newsstands, not including uses defined in Adult Establishment.
 - 34. Paint store.
 - 35. Pet shop.**
 - 36.35. Photographer.**
 - 37.36. Picture framing shop.**
 - 38.37. Reservation center.**

39.38. Restaurants, cafes and fast food establishment.
40.39. Second hand stores.
41.40. Shoe store.
42.41. Sporting goods.
43.42. Stamp and coin stores.
44.43. Tailors and dressmakers.
45.44. Tanning salon.
46.45. Travel agencies.
47.46. Video store, not including uses defined in Adult Establishment.
48.47. Social club and fraternal organizations, not including uses defined in Adult Establishment.
49.48. Telephone exchange.
50.49. Telephone answering service.
51.50. Theater, indoor, not including uses defined in Adult Establishment.
52.51. Public overhead and underground local distribution utilities.

Publicly owned and operated facilities. (Ordinance No. 950, 3-1-05)

5.11.03 Permitted Conditional Uses:

5.11.03.01 Recreational establishments.
 5.11.03.02 Variety store, not including uses defined in Adult Establishment
 5.11.03.03 Amusement arcades.
 5.11.03.04 Bowling center.
 5.11.03.05 Brew Pubs.
 5.11.03.06 Micro breweries when in conjunction with a restaurant.
 5.11.03.07 Coffee Kiosks.
 5.11.03.08 Automated Teller Machines when not within the interior of a primary use.
 5.11.03.09 Business or trade school.
 5.11.03.10 Garden supply and retail garden center.
 5.11.03.11 Commercial greenhouse.
 5.11.03.12 Mail order services.
 5.11.03.13 Pinball or video games business.
 5.11.03.14 Tavern and cocktail lounge, not including uses defined in Adult Establishment.
 5.11.03.15 Totally enclosed, automated and conveyor-style car washes.
 5.11.03.16 Convenience store with limited fuel sales.
 5.11.03.17 Residences in conjunction with the principal use when located above the ground floor.
 5.11.03.18 Churches, temples, seminaries, and convents including residences for teachers and
 pastors.
 5.11.03.19 Car wash.
 5.11.03.20 Retail building material sales; provided that the following minimum standards are
 present:
 1. All lumber shall be enclosed with the primary structure.
 2. All year round landscaping materials shall be enclosed within the primary
 structure.
 3. All outdoor storage shall be temporary and shall comply with the provisions for
 Temporary Uses, as per this Ordinance.
 5.11.03.21 Service station with minor automobile repair services.
5.11.03.22 Tire store and minor automobile repair service.
5.11.03.23 *Animal Specialty Services with or without overnight boarding of animals and outdoor
 exercise areas.*

5.11.03.24 *Pet shop.*

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

5.11.04 Permitted Temporary Uses

Temporary Uses require a permit from the City of La Vista and shall be valid only for a specific amount of time as indicated on said permit. *All platted lots or tracts of land may have a maximum number of four (4) temporary uses per calendar year. Such uses shall not last more than two (2) weeks per use, except as provided for hereafter. (Ordinance No. 998, 7-18-06)*

- 5.11.04.01 Temporary greenhouses.
- 5.11.04.02 Temporary structures as needed for sidewalk and other outdoor sales events.
- 5.11.04.03 Fireworks stands, provided the criteria are met as established by the City through separate Ordinances.
- 5.11.04.04 Buildings and uses incidental to construction work *are permitted to remain until completion or abandonment of the construction work, at which time they shall be removed. (Ordinance No. 998, 7-18-06)*
- 5.11.04.05 Temporary structure for festivals or commercial events.

5.11.05 Permitted Accessory Uses

- 5.11.05.01 Buildings and uses customarily incidental to the permitted uses.
- 5.11.05.02 Parking as permitted in Section 7.05 through 7.09.
- 5.11.05.03 Signs allowed in Section 7.01 through 7.04.
- 5.11.05.04 Landscaping as required by Section 7.17.

5.11.06 Height and Lot Requirements:

- 5.11.06.01 The height and minimum lot requirements shall be as follows:

<i>Uses</i>	Lot Area (SF)	Lot Width	Front Yard	Side Yard	Rear Yard	Max. Height	Max. Lot Coverage
Permitted Uses	10,000	-	25 ¹	15'	15'	45'	60%
Permitted Conditional Uses	10,000	-	25 ¹	15'	15'	45'	60%

¹. 25' front yard setback required only when no parking is present in the front yard. If parking is located in the front yard then front yard setback is a minimum of fifty (50) feet.

5.11.07 Use Limitations:

- 5.11.07.01 When adjacent to residentially zoned land, no parking, drives or signs shall be allowed in any required yard within fifteen (15) feet of such district. Furthermore, permanent screening shall be provided in this area in order to minimize impacts on residentially zoned property, as per Section 7.14.04.
- 5.11.07.02 Exterior lighting fixtures shall be shaded so that no direct light is cast upon any residential property and so that no glare is visible to any traffic on any public street.

Section 2.02 Definitions

Section 2.02 – Definitions: A

2.02.01 ABANDONMENT shall mean to cease or discontinue a use or activity without intent to resume as distinguished from short term interruptions such as during periods of remodeling, maintenance, or normal periods of vacation or seasonal closure. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.02 ABUT, ABUTTING shall mean to border on, being contiguous with or have property or district lines in common, including property separated by an alley. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.03 ACCESS OR ACCESS WAY shall mean the place, means, or way by which pedestrians and vehicles shall have safe, adequate and usable ingress and egress to a property or use as required by this Regulation. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.04 ACCESSORY BUILDING (see Building, accessory) ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.05 ACCESSORY STRUCTURE shall mean a detached subordinate structure located on the same lot with the principal structure, the use of which is incidental and accessory to that of the principal structure. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.06 ACCESSORY USE shall mean a use incidental, related, appropriate and clearly subordinate to the main use of the lot or building, which accessory use does not alter the principal use of the subject lot or affect other properties in the district. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.07 ADJACENT shall mean near, close, or abutting; for example, an Industrial District across the street or highway from a Residential District shall be considered as "Adjacent". ← **Formatted:** Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 0.5"

2.02.08 ADULT BOOKSTORE shall mean any premises from which minors are excluded and in which the retail sale of books, magazines, newspapers, movie films, devices, slides, or other photographic or written reproductions is conducted as a principal use of the premises, if such services are distinguished or characterized by an emphasis on "specified sexual activities" or "specified anatomical areas." *(Ordinance No. 1083, 2-17-09)* ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.09 ADULT COMPANIONSHIP ESTABLISHMENT shall mean an establishment which provides the service of engaging in or listening to conversation, talk or discussion between an employee of the establishment and a customer, if such service is distinguished or characterized by an emphasis on "specified sexual activities" or "specified anatomical areas." ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.10 ADULT ENTERTAINMENT ESTABLISHMENT shall mean any business which offers its patrons services or entertainment characterized by an emphasis on matter depicting, exposing, describing, discussing or relating to "specified sexual activities" or "specified anatomical areas," including, but without limitation, adult bookstores, adult motion picture theaters, *adult* saunas, adult companionship establishments, adult health clubs, adult cabarets, adult novelty businesses, adult motion picture arcades, adult modeling studios, adult hotel or motel, *adult* internet industries, and *adult* massage parlor / health club. *(Ordinance No. 1083, 2-17-09)* ← **Formatted:** Tab stops: Not at 0.38" ← **Formatted:** Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 0.5"

2.02.11 ADULT HOTEL OR MOTEL shall mean a hotel or motel from which minors are specifically excluded from patronage and wherein material is presented which is distinguished or characterized by an emphasis on matter depicting, describing or relating to "specified sexual activities" or "specified anatomical areas." ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.12 ADULT INTERNET INDUSTRIES shall mean any business within an enclosed building or outdoors that is producing materials for distribution on the Internet, including live video streaming, tape delayed video broadcasts, live ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

simulcasting, still photographs, audio broadcasts, animated video or hard copy, wherein material is presented which is distinguished or characterized by an emphasis on matter depicting, describing or relating to "specified sexual activities" or "specified anatomical areas." Said uses are intended for viewing by other parties while on-line and for a specified charge. (Ordinance No. 891, 2-04-03); (Ordinance No. 1083, 2-17-09)

2.02.13 ADULT MASSAGE PARLOR, HEALTH CLUB shall mean a massage parlor or health club, which restricts minors by reason of age, and which provides the services of massage, if such service is distinguished or characterized by an emphasis on "specified sexual activities" or "specified anatomical areas."

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.14 ADULT MINI-MOTION PICTURE THEATER shall mean a business premises within an enclosed building with a capacity for less than 50 persons used for presenting visual-media material if such business as a prevailing practice excludes minors by virtue of age, or if said material is distinguished or characterized by an emphasis on the depiction or description of "specified sexual activities" or "specified anatomical areas" for observation by patrons therein.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.15 ADULT MOTION PICTURE ARCADE shall mean any place to which the public is permitted or invited wherein coin or slug-operated or electronically, electrically or mechanically controlled still or motor picture machines, projectors or other image-producing devices are maintained to show images to five or fewer persons per machine at any one time, and where the images so displayed are distinguished or characterized by an emphasis on depicting or describing "specified sexual activities" or "specified anatomical areas."

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.16 ADULT MOTION PICTURE THEATERS shall mean a business premises within an enclosed building with a capacity of 50 or more persons used for presenting visual media material if said business as a prevailing practice excludes minors by virtue of age, or if said material is distinguished or characterized by an emphasis on the depiction of description of "specified sexual activities" or "specified anatomical areas" for observation by patrons therein.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.17 ADULT NOVELTY BUSINESS shall mean a business which has as a principal activity of the sale of devices which simulate human genitals or devices which are designed for sexual stimulation.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.18 ADULT SAUNA shall mean a sauna which excludes minors by reason of age, or which provides a steam bath or heat bathing room used for the purpose of bathing, relaxation, or reducing, utilizing steam or hot air as a cleaning, relaxing or reducing agent, if the service provided by the sauna is distinguished or characterized by an emphasis on "specified sexual activities" or "specified anatomical areas."

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.19 ADVERTISING STRUCTURE shall mean any notice or advertisement, pictorial or otherwise, and all such structures used as an outdoor display, regardless of size and shape, for the purposes of making anything known, the origin or place of sale of which is not on the property with such Advertising Structure.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.20 AGRICULTURAL AND FARM BUILDINGS AND STRUCTURES shall mean any building or structure which is necessary or incidental to the normal conduct of a farm including but not limited to residence of the operator, residence of hired men, barns, buildings and sheds for housing livestock, poultry and farm machinery, buildings for the storage or shelter of grain, hay and other crops, silos, windmills and water storage tanks.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.21 AGRICULTURE shall mean the use of land for agricultural purposes, of obtaining a profit by raising, harvesting, and selling crops or by the feeding, breeding, management, and sale of, or the produce of, livestock, poultry, fur-bearing animals, or

Formatted: Indent: Left: 1.38", No bullets or numbering

honeybees, or for dairying and the sale of dairy products, or any other agricultural or horticultural use. Agricultural use shall not be construed to include any parcel of land of less than twenty acres or any non-agricultural commercial or industrial development.

2.02.22 AIRPORT shall mean any area which is used or is intended to be used for the taking off and landing of aircraft, including helicopters, and any appurtenant areas which are used or are intended to be used for airport buildings or facilities, including open spaces, taxiways, and tie-down areas.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.23 ALLEY shall mean a minor public service street or public thoroughfare 20 feet or less in width, through a block of lots primarily for vehicular service access to the rear or side of properties otherwise abutting on another street. Buildings facing an alley shall not be construed as satisfying the requirements of this regulation related to frontage on a dedicated street.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.24 ALTERATION shall mean any change, addition or modification in construction or occupancy of an existing structure.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.25 AMENDMENT shall mean a change in the wording, context, or substance of this Regulation, an addition or deletion or a change in the district boundaries or classifications upon the zoning map.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.26 AMUSEMENT ARCADE shall mean a building or a part of a building where five or more pinball machines, video games, or other similar player-orientated amusement devices are available and are maintained for use.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.27 ANIMAL HOSPITAL (see Hospital, animal)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.28 ANIMAL SPECIALTY SERVICES shall refer to establishments primarily engaged in pet grooming, clipping, bathing, daycare, training courses, obedience classes, and similar services. Does not include veterinary services, but may include or overnight boarding of animals-kennels. (Ordinance No. 1053, 1-15-08)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.29 ANTENNA shall mean any attached or external system of wires, poles, rods, reflecting disks or similar devices used for the transmission or reception of electromagnetic waves. (Also, see Satellite Dish Antenna.)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.30 ANTIQUE STORE shall mean a place offering primarily antiques for sale. An antique for the purpose of this ordinance shall be a work of art, piece of furniture, decorative object, or the like, belonging to the past, at least 30 years old. (Ordinance No. 1083, 2-17-09)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.31 APARTMENT shall mean a room or a suite of rooms within an apartment house or multiple family dwelling arranged, intended or designed for a place of residence of a single family or group of individuals living together. (Also, see Dwelling Unit)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.32 APPAREL SHOP shall mean retail stores where clothing is sold, such as department stores, shoe stores, and dress, hosiery, and millinery shops. (Ordinance No. 1083, 2-17-09)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.33 APPLIANCE STORE shall refer to retail shops selling equipment used for domestic functions. A store may include heavy appliances such as refrigerators, washers, dryers, ovens, dishwashers, or other similar domestic equipment. The store may also include smaller appliances such as televisions, computers, radios, microwaves, and other similar domestic equipment. (Ordinance No. 1083, 2-17-09)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.34 APPEARANCE shall mean the outward aspect visible to the public.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.35 APPROPRIATE shall mean the sympathetic, or fitting, to the context of the site and the whole community. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.36 APPURTEANCES shall mean the visible, functional objects accessory to and part of buildings. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.37 ARCHITECTURAL CANOPY SIGN (see Sign, architectural canopy) ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.38 ARCHITECTURAL CHARACTER (see Architectural Concept) ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.39 ARCHITECTURAL CONCEPT shall mean the basic aesthetic idea of a building, or group of buildings or structures, including the site and landscape development. *(Ordinance No. 1083, 2-17-09)* ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.40 ARCHITECTURAL FEATURE shall mean a prominent or significant part or element of a building, structure, or site. Architectural features may include special lines, massing, and/or texture. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.44.01 LINES shall mean visual elements of the building, either within the façade or on the building edge, which are in a linear form either horizontally or vertically and may be composed of masonry, glass, or other related materials. ← **Formatted:** Indent: Left: 0.75", First line: 0"

2.02.44.02 MASS shall pertain to the volume or bulk of a building or structure. ← **Formatted:** Indent: Left: 0.5"

2.02.44.03 TEXTURE shall mean the quality of a surface, ranging from mirror finish, smooth, to coarse and unfinished. ← **Formatted:** Indent: Left: 0.75", First line: 0"

2.02.41 ARCHITECTURAL STYLE shall mean the characteristic form and detail, as of buildings of a particular historic period. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.42 ART GALLERY shall mean an establishment engaged in the sale, loan, or display of art books, paintings, sculpture, or other works of art. This clarification does not include libraries, museums, or non-commercial art galleries. *(Ordinance No. 1083, 2-17-09)* ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.43 ASSISTED LIVING FACILITIES shall mean a type of long-term care facility for elderly or disabled people needing assistance with daily activities such as eating, bathing, dressing, laundry, housekeeping, and medicating. These facilities typically have a central cafeteria and nursing staff on call. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.44 ATTACHED shall mean attached to real estate in such a way as to require dismantling, cutting away, unbolting from a permanent foundation or structural change in such structure in order to relocate it to another site. *(Ordinance No. 1083, 2-17-09)* ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.45 AUCTION SALES shall mean a building or structure or lands used for the storage of goods, materials or livestock which are to be sold on the premises by public auction and for the sale of the said goods, materials or livestock by public auction and on an occasional basis. Auction sales also includes motor vehicle wholesale sales, including trailers, trucks, vans, recreational vehicles, boats or motorcycles or other similar motorized transportation vehicles. *(Ordinance No. 891, 2-04-03)* ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.46 AUTOMATED TELLER MACHINE (ATM) shall mean an automated device that performs banking or financial functions at a location remote from the controlling financial institution. *(Ordinance No. 1083, 2-17-09)* ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.47 AUTOMOBILE SALES shall mean the storage and display for sale or lease of more than two motor vehicles or any type of trailer (provided the trailer is unoccupied) at any one time and/or a total of ten or more sold or leased during the course of a calendar year, and where repair or body work is incidental to the operation ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

of the new or used vehicle sales or leasing. Automobile sales includes all motor vehicle retail sales and leases including trucks, vans, recreational vehicles, boats or motorcycles or other similar motorized transportation vehicles. (Also, see Auction Sales) (Ordinance No. 891, 2-04-03)

2.02.48 AUTOMOTIVE REPAIR SERVICES shall refer to any building, structure, improvements, or land used for the repair and maintenance of automobiles, motorcycles, trucks, trailers, or similar vehicles including but not limited to body, fender, muffler, or upholstery work; oil change and lubrication; major painting services; collision services; and tire service and sales. (Ordinance No. 1053, 1-15-08)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.49 AUTOMOTIVE SERVICES shall refer to any building, structure, improvements or land used for the general maintenance of automobiles, motorcycles, trucks, trailers or similar vehicles including but not limited to washing, cleaning, and/or detailing; installation of car stereos, accessories, or other light equipment; and minor painting. (Ordinance No. 1053, 1-15-08)

Formatted: Indent: Left: 1.38", No bullets or numbering

Section 2.03 - Definitions: B

Formatted: Font: 10 pt

2.02.50 BAKERY SHOP shall mean an establishment primarily engaged in the retail sale of baked products. The products may be prepared either on or off site. A bakery shall be considered a general retail use. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.51 BANK shall mean a freestanding building or secondary use within a building, with or without a drive-up window, for the custody, loan, or exchange of money; for the extension of credit; and for facilitating the transmission of funds. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.52 BASEMENT shall mean a building space partly underground, and having at least one-half (1/2) of its height, measuring from its floor to its ceiling, above the average adjoining finished ground grade line.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.53 BEACON shall mean any light with one or more beams directed into the atmosphere or directed at one or more points not on the same zone lot as the light source; also, any light with one or more beams that rotate or move.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.54 BEAUTY SHOP shall mean any establishment where cosmetology services are provided including hair care, nail care, and skin care on a regular basis for compensation. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.55 BED and BREAKFAST shall mean a house, or portion thereof, where short-term lodging rooms and meals are provided. The operator shall live on the premises. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.56 BEDROOM shall mean a room within a dwelling unit planned and intended for sleeping, separated from other rooms by a door.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.57 BERM shall mean a raised form of earth to provide screening or to improve the aesthetic character.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.58 BILLBOARD (see Sign, Billboard)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.59 BLOCK shall mean a parcel of land platted into lots and bounded by public streets or by waterways, rights-of-way, unplatted land, City-County boundaries, or adjoining property lines.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.60 BOARD OF ADJUSTMENT shall mean that board that has been created by the city and which has the statutory authority to hear and determine appeals, interpretations of, and variances to the zoning regulations. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.61 BOARDING HOUSE shall mean a building containing a single dwelling unit and provisions for not more than five (5) guests, where lodging is provided with or without meals for compensation. (Also, see *Bed and Breakfast*) (*Ordinance No. 1083, 2-17-09*) ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.62 BOOK STORE shall mean a retail establishment that, as its primary business, engages in the sale, rental, or other charge-for-use of books, magazines, newspapers, greeting cards, postcards, videotapes, computer software, or any other printed or electronically conveyed information or media, excluding any uses defined as "adult entertainment establishments." (*Ordinance No. 1083, 2-17-09*) ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.63 BOWLING CENTER shall mean an establishment that devotes more than 50 percent of its gross floor area to bowling lanes, equipment, and playing area. Accessory uses such as the retail sale of snacks, the retail sale of beverages, and a video game arcade are customary. (*Ordinance No. 1083, 2-17-09*) ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.64 BREW-ON PREMISES STORE shall mean a facility that provides the ingredients and equipment for a customer to use to brew malt liquor at the store. Brew-on-premises stores do not include the sale of intoxicating liquor, unless the owner of the brew-on-premises store holds the appropriate liquor license. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.65 BREW PUB shall mean a restaurant or hotel which includes the brewing of beer as an accessory use. The brewing operation processes water, malt, hops, and yeast into beer or ale by mashing, cooking, and fermenting. By definition, these establishments produce no more than 10,000 barrels of beer or ale annually. The area, by definition, used for brewing, including bottling and kegging, shall not exceed twenty-five (25) percent of the total floor area of the commercial space. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.66 BUFFER shall mean a strip of land established to protect one type of land use from another incompatible land use or between a land use and a private or public road. (Also, see *Screening*) ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.67 BUILDING shall mean any structure built and maintained for the support, shelter or enclosure of persons, animals, chattels, or property of any kind, but shall not include temporary buildings as defined in "Structure, Temporary". Trailers, with or without wheels, shall not be considered as buildings. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.68 BUILDING, ACCESSORY shall mean any detached subordinate building which serves a function customarily incidental to that of the main building or main use of the premises. Customary accessory building includes farm buildings, garages, carports, and small storage sheds. ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.69 BUILDING CODE shall mean the various codes of the City that regulate construction and requires building permits, electrical permits, mechanical permits, plumbing permits, and other permits to do work regulated by the Uniform Building Code, ← **Formatted:** Indent: Left: 1.38", No bullets or numbering

Example 1 : Building Height Measurements

and other codes adopted by the City that pertain to building construction.

2.02.70 BUILDING HEIGHT shall mean the vertical distance above grade to the highest point of the coping of a flat roof or to the deck line of a mansard roof, or to the average height of the highest gable of a pitched, hipped, or shed roof, measured from the highest adjoining sidewalk or ground surface within a five (5) foot horizontal distance at the exterior wall of the building. (Also, see Height) (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.71 BUILDING INSPECTOR shall mean the *Chief Building Official* of the City of La Vista, Nebraska. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.72 BUILDING SETBACK LINE shall mean the minimum of distance as prescribed by this regulation between any property line and the closest point of the building line or face of any building or structure related thereto.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.73 BUSINESS OR TRADE SCHOOL (*see Special or Vocational Training Facilities*) (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.74 BUSINESS SERVICES shall mean establishments primarily engaged in rendering services to business establishments on a contract or fee basis, such as advertising, credit reporting, collection of claims, mailing, reproduction, stenographic, news syndicates, computer programming, photocopying, duplicating, data processing, services to buildings, and help supply services. (See also *Standard Industrial Classification (SIC) Major Group 73, published by the U.S. Department of Labor.*) (*Ordinance No. 1053, 1-15-08*)

Formatted: Indent: Left: 1.38", No bullets or numbering

Section 2.04 - Definitions: C

Formatted: Font: 10 pt

2.02.75 CAMPGROUND shall mean a parcel of land intended for the temporary occupancy of tents, campers, and recreational vehicles and which primary purpose is recreational, having open areas that are natural in character.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.76 CAR WASH shall mean a building or structure or an area of land with machine or hand operated facilities for the cleaning, washing, polishing, or waxing of motor vehicles, not including semi-trailer tractors, buses, and commercial fleets.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.77 CARPORT shall mean a permanent roofed structure with not more than two (2) enclosed sides used or intended to be used for automobile shelter and storage.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.78 CELLAR shall mean a building space having more than one-half (1/2) of its height below the average adjoining grade lines.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.79 CEMETERY shall mean land used or intended to be used for the burial of the dead and dedicated for such purposes, including columbariums, crematoriums, and mausoleums.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.80 CHANGEABLE COPY shall refer to a sign or portion thereof with characters, letters, or illustrations that can be changed or rearranged without, altering the face or the surface of the sign. A sign on which the message changes more than eight times per day shall be considered an animated sign and not a changeable copy sign for purposes of this ordinance. A sign on which the only copy changes is an electronic or mechanical indication of time or temperature shall be considered a "time and temperature" portion of a sign and not a changeable copy sign for purposes of this ordinance. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.81 CHANNEL shall mean the geographical area within either the natural or artificial banks of a watercourse or drainway.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.82 **CHARITABLE ORGANIZATION or CLUB** shall mean a public or semi-public institutional use of a philanthropic, charitable, benevolent, religious, or eleemosynary character, but not including sheltering or caring of animals. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.83 **CHILD CARE CENTER** shall mean an establishment other than a public or parochial school, which provides day care, play groups, nursery schools or education for thirteen (13) or more children under age 13, at any one time, from families other than that of the provider. In addition to these regulations, Child Care Centers shall meet all requirements of the State of Nebraska.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.84 **CHILD CARE HOME** shall mean an operation in the provider's place of residence which serves at least four (4), but not more than eight (8) children at any one time, from families other than that of the provider. A Family Child Care Home I provider may be approved to serve no more than two (2) additional school-age children during non-school hours. A Family Child Care Home II operation may be either in the provider's own place of residence or a site other than the residence, serving twelve (12) or fewer children at any one time. In addition to these regulations, Child Care Homes shall meet all requirements of the State of Nebraska.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.85 **CITY** shall mean the City of La Vista.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.86 **CODE** shall mean the Municipal Code of the City of La Vista.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.87 **COFFEE KIOSK** shall mean a retail food business in a freestanding building that sells coffee, or other beverages, and remade bakery goods from a drive-through window or walk-up window. (*Ordinance No. 1053, 1-15-08*).

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.88 **COLLEGE AND UNIVERSITY** shall mean an educational institution offering advanced instruction in any academic field beyond the secondary level, including trade schools or business colleges. (*Ordinance No. 1168, 3-6-12*)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.89 **COMMISSION** shall mean the La Vista Planning Commission.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.90 **COMMERCIAL MESSAGE** shall mean any sign wording, logo, or other representation that, directly or indirectly, names, advertises, or calls attention to a business, product, service, or other commercial activity. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.91 **COMMON AREA OR PROPERTY** shall mean a parcel or parcels of land, together with the improvements thereon, the use and enjoyment of which are shared by the owners of the individual building sites in a Planned Development or condominium development.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.92 **COMMUNICATION SERVICES** shall mean establishments primarily engaged in the provision of broadcasting and other information relay services accomplished through the use of electronic and telephonic mechanisms. Excluded are facilities classified as major utility services or wireless communication towers. Typical uses include television studios, communication service centers, internet service offices, or film and sound recording facilities. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.93 **COMPATIBILITY** shall mean harmony in the appearance of two or more external design features in the same vicinity.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.94 **COMPATIBLE USES** shall mean a land use which is congruous with, tolerant of, and has no adverse effects on existing neighboring uses. Incompatibility may be affected by pedestrian or vehicular traffic generation, volume of goods handled and environmental elements such as noise, dust, odor, air pollution, glare, lighting,

Formatted: Indent: Left: 1.38", No bullets or numbering

debris generated, contamination of surface or ground water, aesthetics, vibration, electrical interference, and radiation.

2.02.95 COMPREHENSIVE PLAN shall mean the Comprehensive Plan of La Vista, Nebraska as adopted by the City Council, setting forth policies for the present and foreseeable future community welfare as a whole and meeting the purposes and requirements set forth in Section 19-903, R.R.S. 1943, as the same may, from time-to-time, be amended.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.96 CONDITIONAL USE shall mean a use where allowed by the district regulations, that would not be appropriate generally throughout the zoning district without restrictions, but which, if controlled as to number, size, area, location, relation to the neighborhood or other minimal protective characteristics would not be detrimental to the public health, safety, and general welfare.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.97 CONDITIONAL USE PERMIT shall mean a permit issued by the Planning Commission and City Council that authorizes the recipient to make conditional use of property in accordance with the provisions of Article 6 and any additional conditions placed upon, or required by said permit.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.98 CONDOMINIUM shall mean a structure or structures proposed for construction comprising a project in which an undivided interest in the land is coupled with the right to the exclusive occupancy of a designated residential space and/or spaces and accompanying facilities.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.99 CONGREGATE HOUSING shall mean a residential facility for four or more persons fifty-five (55) years or over, their spouses, or surviving spouses, providing living and sleeping facilities including meal preparation, dining areas, laundry services, room cleaning and common recreational, social, and service facilities for the exclusive use of all residents including resident staff personnel who occupy a room or unit in the residential facility. (Also see Housing for the elderly)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.100 CONSERVATION shall mean the protection and care that prevent destruction or deterioration of historical or otherwise significant structures, buildings or natural resources.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.101 CONSERVATION AREA shall mean environmentally sensitive and valuable lands protected from any activity that would significantly alter their ecological integrity, balance or character, except in overriding public interest, including but not limited to: wetlands, floodways, flood plains, drainage ways, river or stream banks, and areas of significant biological productivity or uniqueness.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.102 CONSERVATION EASEMENT shall mean an easement granting a right or interest in real property that is appropriate to retaining land or water areas predominantly in their natural, scenic, open, or wooded condition and retaining such areas as suitable habitat for fish, plants, or wildlife, or maintaining existing land uses.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.103 CONSTRUCTION shall mean on-site erection, fabrication, installation, alteration, demolition, or removal of any structure, facility, or addition thereto, including all related activities, but not restricted to, clearing of land, earth moving, blasting and landscaping. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.104 CONTIGUOUS shall mean the same as "Abut".

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.105 CONTINUING CARE RETIREMENT COMMUNITY shall offer services and housing packages that allow access to senior independent living, assisted living, and nursing care facilities. Seniors who are independent may live in a single-family home, apartment or condominium within the Continuing Care Retirement Community.

Formatted: Indent: Left: 1.38", No bullets or numbering

When members of the community begin to need help with activities of daily living (e.g. bathing, dressing, eating, etc.), they may be transferred to an assisted living or nursing care facility on the same site.

2.02.106 CONVENIENCE STORE shall mean a one-story, retail store that is designed and stocked to sell primarily food, beverages, and other household supplies to customers who purchase only a relatively few items (in contrast to a "supermarket.") It is dependent on, and is designed to attract and accommodate large volumes of stop-and-go traffic. *Fuel sales shall be limited to automobiles, pick-up trucks, boats, recreational vehicles, motorcycles, and small motorized equipment.* (Ordinance No. 1083, 2-17-09)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

Section 2.05 - Definitions: D

2.02.107 DENSITY shall mean the number of dwelling units per gross acre of land.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.108 DEVELOPER shall mean any person, corporation, partnership, or entity that is responsible for any undertaking that requires a building or zoning permit, conditional use permit or sign permit.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.109 DEVELOPMENT shall mean any manmade change to improved or unimproved real estate, including but not limited to buildings or other structures, mining, dredging, filling, grading, paving, excavation, or drilling operations for which necessary permits may be required. *Also, shall mean any material change in the use or appearance of any structure or in the land itself; the division of land into separate lots; any change in the intensity or use of land, such as an increase in the number of dwelling units in a structure or a change to a commercial or industrial use from a less intensive use; any activity that alters a river, stream, lake, pond, woodland, wetland, endangered species habitat, aquifer or other resource area.* (Ordinance No. 1083, 2-17-09)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.110 DOG KENNEL (See Kennel)

← **Formatted:** Indent: Left: 0.06"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.111 DOWNZONING shall mean a change in zoning classification of land to a less intensive or more restrictive district such as from commercial district to residential district or from a multiple family residential district to single family residential district.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.112 DRAINAGE shall mean the removal of surface water or groundwater from land by drains, grading, or other means that include runoff controls to minimize erosion and sedimentation during and after construction or development, the means for preserving the water supply, and the prevention or alleviation of flooding. (Ordinance No. 1083, 2-17-09)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.113 DRIVEWAY shall mean any vehicular access to an off-street parking or loading facility.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.114 DUPLEX shall mean the same as "Dwelling, Two (2) Family".

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.115 DWELLING Any building or portion thereof which is designed and used exclusively for single family residential purposes, excluding mobile homes.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.116 DWELLING, MOBILE HOME Any prefabricated structure, composed of one or more parts, used for living and sleeping purposes, shipped or moved in essentially a complete condition and mounted on wheels, skids or rollers, jacks blocks, horses, skirting or a permanent or temporary foundation or any prefabricated structure which has been or reasonably can be equipped with wheels or other devices for transporting the structure from place to place, whether by motive power or other means. The term mobile home shall include trailer home and camp car, but the definition shall not apply to any vehicle lawfully operated upon fixed rails.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.116.1 Permanently Attached: Attached to real estate in such a way as to require dismantling, cutting away, unbolting from permanent continuous foundation or structural change in such mobile home in order to relocate it on another site in accordance to manufacturers recommendations.

Formatted: Indent: Left: 1.75", No bullets or numbering

2.02.116.2 Permanent Foundation: Base on which building rests to be constructed from either poured concrete or laid masonry block or brick placed on a footing located below ground level to a point below the frost line. (*Ordinance No. 1083, 2-17-09*)

2.02.117 **DWELLING, MULTIPLE FAMILY** shall mean a building or buildings designed and used for occupancy by three (3) or more families, all living independently of each other and having separate kitchen and toilet facilities for each family. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.118 **DWELLING, SINGLE FAMILY** a building having accommodations for or occupied exclusively by one family which meet all the following standards:

2.02.118.1. The home shall have no less than nine hundred (900) square feet of floor area, above grade, for single story construction;

2.02.118.2 The home shall have no less than an eighteen (18) foot exterior width;

2.02.118.3. The roof shall be pitched with a minimum vertical rise of two and one-half (2 1/2) inches for each twelve (12) inches of horizontal run;

2.02.118.43. The exterior material shall be of a color, material and scale comparable with those existing in residential site-built, single family construction;

2.02.118.54. The home shall have a non-reflective roof material that is or simulates asphalt or wood shingles, tile, or rock;

2.02.118.6 The home shall be placed on a continuous permanent foundation and have wheels, axles, transporting lights, and removable towing apparatus removed;

2.02.118.75. The home shall meet and maintain the same standards that are uniformly applied to all single-family dwellings in the zoning district; and

2.02.118.86. Permanent foundation: continuous perimeter base on which building rests to be constructed from either poured concrete or laid masonry block or brick placed on a footing located below ground level to a point below the frost line. (*Ordinance No. 1083, 2-17-09*)

Formatted: Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 2" + Indent at: 2.25"

Formatted: Indent: Left: 1.75", No bullets or numbering

Formatted: Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 2" + Indent at: 2.25"

Formatted: Indent: Left: 1.75", No bullets or numbering

Formatted: Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 2" + Indent at: 2.25"

2.02.119 **DWELLING, TWO (2) FAMILY** shall mean a building designed or used exclusively for the occupancy of two (2) families living independently of each other and having separate kitchen and toilet facilities for each family.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.120 **DWELLING UNIT** One room, or rooms connected together, constituting a separate, independent housekeeping establishment for owner occupancy or lease on a weekly, monthly, or longer basis, and physically separate from any other rooms or dwelling units which may be in the same structure, and containing independent cooking, toilet and sleeping facilities.

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Section 2.06 - Definitions: E

2.02.124 **EASEMENT** shall mean a space or a lot or parcel of land reserved for or used for public utilities or public or private uses.

Formatted: Tab stops: Not at 0.5"

Formatted: Tab stops: Not at 0.5"

2.02.122 **EDUCATIONAL FACILITY** shall mean a public or nonprofit institution or facility which conducts regular academic instruction at preschool, kindergarten, elementary, secondary, and collegiate levels, including graduate schools, universities,

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

junior colleges, trade schools, nonprofit research institutions and religious institutions. Such institutions must either: (1) Offer general academic instruction equivalent to the standards established by the State Board of Education; or (2) Confer degrees as a college or university or undergraduate or graduate standing; or (3) Conduct research; or (4) Give religious instruction. Private schools, academies, or institutes incorporated or otherwise, which operate for a profit, commercial, or private trade schools are not included in this definition. (*Ordinance No. 1083, 2-17-09*)

2.02.123 EFFECTIVE DATE shall mean the date that this Ordinance shall have been adopted, amended, or the date land areas became subject to the regulations contained in this Ordinance as a result of such adoption or amendment.

2.02.124 ENCROACHMENT shall mean an advancement or intrusion beyond the lines or limits as designated and established by the Regulation, and to infringe or trespass into or upon the possession or right of others without permission.

2.02.125 ENLARGEMENT shall mean the expansion of a building, structure, or use in volume, size, area, height, length, width, depth, capacity, ground coverage, or in number.

2.02.126 ENTERTAINMENT VENUE shall mean any activity that includes, but is not limited to, a theatrical performance, live music performance, live or "virtual" disc jockey, or live or "virtual" master of ceremonies, held indoors or outdoors to which members of the public are invited with or without charge. (*Ordinance No. 1219, 7-15-14*)

2.02.127 ERECTED shall mean constructed upon or moved onto a site.

2.02.128 EVENT CENTER shall mean all buildings and associated parking facilities which are kept, used, maintained, advertised, held out, leased out, or otherwise made available to private groups and/or the general public for such purposes as meetings, civic, educational, political, religious or social purpose such as receptions, dances, entertainment, secondhand merchandise sales and the like, and may include a banquet hall, private club or fraternal organization, but not including uses defined in Adult Establishment. (*Ordinance No. 955, 7-19-05*)

2.02.129 EXERCISE, FITNESS and TANNING SPA shall mean an establishment that provides exercise facilities for the purposes of running, jogging, aerobics, weight lifting, court sports, and/or swimming, as well as locker rooms, showers, massage rooms, tanning beds, hot tubs, saunas or other related accessory uses; however, excluding any uses defined as "adult entertainment establishments". (*Ordinance No. 1083, 2-17-09*)

2.02.130 EXTERNAL DESIGN FEATURE shall mean the general arrangement of any portion of a building, sign, landscaping, or structure and including the kind, color, and texture of the materials of such portion, and the types of roof, windows, doors, lights, attached or ground signs, or other fixtures appurtenant to such portions as will be open to public view from any street, place, or way.

2.02.134 EXTRATERRITORIAL JURISDICTION shall mean the area beyond the corporate limits, in which the City has been granted the powers by the state to exercise zoning and building regulations and is exercising such powers.

Section 2.07 - Definitions: F

2.02.132 FACADE shall mean the exterior wall of a building exposed to public view from the building's exterior.

2.02.133 FACTORY shall mean a structure or plant within which something is made or manufactured from raw or partly wrought materials into forms suitable for use.

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.02.134 FAMILY shall mean *a person living alone, or any of the following groups living together as a single nonprofit housekeeping unit and sharing common living, sleeping, cooking, and eating facilities: (1) any number of people related by blood, marriage, adoption, guardianship, or duly-authorized custodial relationship; (2) up to four unrelated people and any related children; and (3) a group care home.*

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Family does not include any society, club, fraternity, sorority, association, lodge, organization, group of students, or other individuals where the common living arrangement is temporary or seasonal. Also, the term does not include any group of individuals who are in a group living arrangement as a result of criminal offenses. (Ordinance No. 1083, 2-17-09)

Formatted: Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.75"

2.02.135 FARM an area containing at least twenty (20) acres or more which is used for growing of the usual farm products such as vegetables, fruit, and grain; *storing of such products; and/or* raising farm animals. The term farming includes the operating of such area for two or more of the above uses with the necessary accessory uses for treating or storing the produce and the feeding of livestock as hereinafter prescribed provided such accessory uses do not include the feeding of garbage or offal to swine or other animals. *(Ordinance No. 1083, 2-17-09)*

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.02.136 FEEDLOT shall mean a lot, yard, corral or other area in which livestock are confined, primarily for the purpose of feeding and growth prior to slaughter. The term does not include areas which are used for raising crops or other vegetation or upon which livestock are allowed to graze.

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.02.137 FENCE, OPEN shall mean a fence, including gates, which has fifty percent (50%) or more of the surface area in open spaces which affords direct views through the fence. *(Ordinance No. 1083, 2-17-09)*

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.02.138 FENCE, SEASONAL shall mean a temporary fence constructed of plastic or wood lathe erected and maintained from October through April to prevent snow drifting. *(Ordinance No. 871, 10-15-02)*

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.02.139 FENCE, SOLID shall mean any fence which does not qualify as an open fence.

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.02.140 FESTIVAL shall mean the sale of ethnic specialty, regional, and gourmet foods, art and crafts, live musical entertainment, in an outdoor setting. *(Ordinance No. 1083, 2-17-09)*

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.02.141 FLOOD (see Section 5.18.25 of this Ordinance)

2.02.142 FLOOD PLAIN (see Section 5.18.25 of this Ordinance)

2.02.143 FLOODWAY (see Section 5.18.25 of this Ordinance)

2.02.144 FLOOR AREA whenever the term "floor area" is used in this Regulation as a basis for requiring off-street parking for any structure, it shall be assumed that, unless otherwise stated, said floor area applies not only to the ground floor area but also to any additional stories of said structure. All horizontal dimensions shall be taken from the exterior faces of walls.

2.02.145 FOOD SALES shall mean establishments or places of business primarily engaged in the retail sale of food or household products for home consumption. Typical uses include groceries, delicatessens, meat markets, retail bakeries, and candy shops.

2.02.145.1 **FOOD SALES (LIMITED)** shall mean food sales establishments occupying 10,000 square feet or less of space.

2.02.145.2 **FOOD SALES (GENERAL)** shall mean food sales establishments occupying more than 10,000 square feet of space. Typically a supermarket.

2.02.146 **FRONTAGE** shall mean that portion of a parcel of property which abuts a dedicated public street or highway.

Section 2.08 - Definitions: G

2.02.147 **GARAGE** shall mean a detached accessory building or *an attached* portion of a dwelling for the housing of vehicles, including carports. (*Ordinance No. 1083, 2-17-09*)

2.02.148 **GRADE** shall mean the average of the finished ground level at the center of all walls of a building. In case walls are parallel to and within five feet of a sidewalk, the ground level shall be measured at the sidewalk.

2.02.149 **GREENHOUSE** shall mean a building or premises used for growing plants, preparation of floral arrangements for off-site delivery to customers, cold storage of flowers or dry storage of materials used for agricultural or horticultural purposes.

2.02.150 **GROUND COVER** shall mean plant material used in landscaping which remains less than twelve (12) inches in height at maturity. (Also, see Landscaping)

2.02.154 **GROUP CARE HOME** shall mean a home which is operated under the auspices of an organization which is responsible for providing social services, administration, direction, and control for the home which is designed to provide twenty-four (24) hour care for individuals in a residential setting. *This term does not include any society, club, fraternity, sorority, association, lodge, organization, or group of students or other individuals where the common living arrangement is temporary or seasonal. Also, the term does not include any group of individuals who are in a group living arrangement as a result of criminal offenses.* (*Ordinance No. 1083, 2-17-09*)

2.02.152 **GUNSMITH** shall mean a shop that designs, makes or repairs small firearms. (*Ordinance No. 1083, 2-17-09*)

2.02.153 **GUEST ROOM** shall mean a room which is designed to be occupied by one (1) or more guest for sleeping purposes, having no kitchen facilities, not including dormitories.

Section 2.09 - Definitions: H

2.02.154 **HARD SURFACED** shall mean any surface used for movement of vehicular and / or pedestrians which is properly designed with permeable pavement, bricks, interlocking concrete pavers, asphalt or concrete. (*Ordinance No. 1083, 2-17-09*)

2.02.155 **HARMONY** shall mean a quality that represents an appropriate and congruent arrangement of parts, as in an arrangement of varied architectural and landscape elements.

2.02.156 **HAZARDOUS WASTE / MATERIALS** shall mean waste products of industrial or chemical process including finished surplus, used, contaminated or unwanted fertilizer, herbicide, petroleum products, or other such processed waste material. (*Ordinance No. 1083, 2-17-09*)

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.75", No bullets or numbering, Tab stops: Not at 1.5"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Indent: Left: 1.38", Tab stops: Not at 0.5"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

Formatted: Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.02.157 HEALTH CLUB shall mean privately owned for profit facilities such as gymnasiums, athletic clubs, recreational clubs, reducing salons, and weight control establishments. *(Ordinance No. 1083, 2-17-09)*

← **Formatted:** Tab stops: Not at 0.5"
Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.02.158 HEDGE shall mean a plant or series of plants, shrubs or other landscape material, so arranged as to form a physical barrier or enclosure.

← **Formatted:** Tab stops: Not at 0.5"
Formatted: Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.02.159 HOME OCCUPATION shall mean an "in-home" or "home-based" business, industry, or service (not including uses defined as Adult Entertainment Establishment) operating from within a residential dwelling, or within an accessory structure in a residential zoning district. Home occupations shall be secondary and incidental in nature to the primary residential structure and/or property. Home Occupations shall satisfy the standards set forth in Section 7.10 of the City's Zoning Ordinance.

← **Formatted:** Indent: Left: 1.38", No bullets or numbering, Tab stops: Not at 1"

2.022.02.157.01 Home Occupation I (Major): shall mean Home Occupations that include on-site sales or services and/or one part-time or full-time employee that does not reside on the premises.

← **Formatted:** Indent: Left: 0.75", No bullets or numbering

2.032.02.157.02 Home Occupation II (Minor): shall mean a Home Occupation that is not a Home Occupation I, including the following (a) a Home Occupation in which the sole activity is maintenance and use of an office in the home for telecommuting and/or deriving other income or sales; and (b) home-based craftmaking or cooking, which does not involve on-site sales.

(Ordinance No. 879, 11-19-02)

2.042.02.157.03 Occupations defined as Home Occupation II are exempt from a conditional use permit and Home Occupation License. All Home Occupation I uses are required to have a Home Occupation License. *(Ordinance No. 879, 11-19-02)*

2.02.160 HOME OCCUPATION LICENSE shall mean a license provided to the owner/operator of a home occupation. Such license shall include (but not limited to) the following:

2.051. 2.02.158.01 Application fee in accordance with Master Fee Schedule. *(Ordinance No. 879, 11-19-02)*

2.062. 2.02.158.02 For major Home Occupations requiring a Conditional Use Permit, a minimum of seventy-five percent (75%) of the households within two hundred feet (200') of the proposed home occupation shall indicate no objections, in writing, to the operation of such home occupation. A "no objections" signature form shall be provided by the City and said residents shall sign next to their respective address. *(Ordinance No. 879, 11-19-02)*

2.073. 2.02.158.03 A Conditional Use Permit is required for Home Occupation I uses, except Child Care Homes. *(Ordinance No. 879, 11-19-02)*

← **Formatted:** Not Highlight
Formatted: Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.13", No bullets or numbering, Tab stops: Not at 1"

2.02.161 HOME OCCUPATION PERMIT (see Home Occupation License) *(Ordinance No. 879, 11-19-02)*

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.162 HOME OCCUPATION TAX (see Home Occupation License) *(Ordinance No. 879, 11-19-02)*

2.02.163 HOSPITAL, ANIMAL shall mean a place where animals or pets are given medical or surgical treatment and are cared for during the time of such treatment. Use as a kennel shall be limited to short-time boarding and shall be only incidental to such hospital use. *(Ordinance No. 871, 10-15-02)*

2.02.164 HOTEL shall mean a building or portion thereof, or a group of buildings, offering transient lodging accommodations on a daily rate to the general public and providing services associated with restaurants, meeting rooms, and recreational facilities. *(Ordinance No. 1083, 2-17-09)*

2.02.165 HOUSE TRAILER (see Dwelling, Mobile Home)

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

2.02.166 HOUSEHOLD PET shall mean an animal that is customarily kept for personal use or enjoyment within the home. Household pet shall include but not be limited to domestic dogs, domestic cats, domestic tropical birds, fish, and rodents.

Formatted: Indent: Left: 1.38", No bullets or numbering

Section 2.10 - Definitions: I

2.02.167 INCIDENTAL shall mean a use, which is subordinate to the main use of a premise.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.168 INDOOR RECREATIONAL FACILITY shall refer to use of a facility for purposes of recreation. The use shall be completely enclosed within a building with the exception of retractable roofs. Examples include, but are not limited to sports courts, gymnastics, kart racing, batting cages, practice fields, and miniature golf. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.169 INDUSTRIAL CONDOMINIUM shall mean a structure or structures proposed for construction comprising a project in which an undivided interest in the land is coupled with the right to the exclusive occupancy of a designated industrial or manufacturing space and/or spaces and accompanying facilities.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.170 INDUSTRY shall mean the manufacture, fabrication, processing reduction or destruction of any article, substance or commodity, or any other treatment thereof in such a manner as to change the form, character, or appearance thereof and including storage elevators, truck storage yards, warehouses, wholesale storage and other similar types of enterprise.

Formatted: Tab stops: Not at 2.75"

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.171 INOPERABLE MOTOR VEHICLE shall mean any motor vehicle which: (1) Does not have a current state license plate; or, (2) Which may or may not have a current state license plate, but is disassembled or wrecked in part or in whole, or is unable to move under its own power, or is not equipped as required by Nebraska State Law for operation upon streets or highways. A vehicle which is wholly or partially dismantled shall not be considered inoperable when said vehicle is inside a completely enclosed building.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.172 INTENSITY shall mean the degree to which land is used referring to the levels of concentration or activity in uses ranging from uses of low intensity being agricultural and residential to uses of highest intensity being heavy industrial uses. High intensity uses are normally uses that generate concentrations of vehicular traffic and daytime population and are less compatible with lower intensive uses.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.173 INTENT AND PURPOSE shall mean that the Commission and Council by the adoption of this Ordinance have made a finding that the health, safety, and welfare of the community will be served by the creation of the zoning districts and by the regulations prescribed therein.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Section 2.11 - Definitions: J

2.02.174 JUICE BAR (See Adult Establishment)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.175 JUNK shall be any worn-out, cast-off, old, or discarded articles of scrap, copper, brass, iron, steel, rope, rags, batteries, paper, trash, rubber, debris, waste, dismantled or wrecked automobiles, or parts thereof, and other old or scrap ferrous or nonferrous material.

Section 2.12 - Definitions: K

2.02.176 KENNEL shall mean an establishment where three (3) or more dogs, cats, or other household pets, or non-farm/non-domestic or any combination of five (5) or more thereof, at least four (4) months of age are boarded as a business. (*Ordinance No. 1083, 2-17-09*)

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

► **Formatted:** Indent: Left: 1.38", No bullets or numbering

Section 2.13 - Definitions: L

2.02.177 LABORATORY shall mean a facility used for testing and analyzing medical and dental samples from off-site locations. Testing laboratories shall refer to soil and geotechnical research and analysis. Laboratories do not include human or animal research / testing facilities. (*Ordinance No. 1083, 2-17-09*)

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

► **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.178 LANDSCAPE shall mean plant materials, topography, and other natural physical elements combined in relation to one another and to man-made structures.

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

► **Formatted:** Indent: Left: 1.38", No bullets or numbering

► **Formatted:** Tab stops: Not at 0.5"

► **Formatted:** Indent: Left: 1.38", No bullets or numbering

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

► **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.179 LANDSCAPING shall include the original planting of suitable vegetation in conformity with the requirements of this Regulation and the continued maintenance thereof.

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

2.02.180 LAUNDRY SERVICE shall mean an establishment that provides home-type washing, drying, and/or ironing facilities for customers on the premises. (*Ordinance No. 1083, 2-17-09*)

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

► **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.184 LOADING AREA shall mean an off-street space or berth on the same lot with a main building, or contiguous to a group of buildings, for the temporary parking of commercial vehicles while loading or unloading, and which abuts a street, alley, or other appropriate means of ingress and egress. (*Ordinance No. 1083, 2-17-09*)

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

► **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.182 LOGIC OF DESIGN shall mean accepted principles and criteria of validity in the solution of the problem of design.

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

► **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.183 LOT shall mean a parcel or tract of land which is or may be occupied by a use herein permitted, together with yards, and other open spaces herein required, that has frontage upon a street, and is a part of a recorded subdivision plat or has been recorded prior to the adoption of the Regulation, or a parcel of real property delineated on an approved record of survey, lot-split or sub-parceling map as filed in the office of the County Register of Deeds and abutting at least one (1) public street or right-of-way, two (2) easements with dedicated public access, or one (1) private road. (*Ordinance No. 1083, 2-17-09*)

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

2.02.184 LOT AREA shall mean the total area, on a horizontal plane, within the lot lines of a lot.

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

► **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.02.185 LOT, CORNER shall mean a lot located at the intersection of two (2) or more streets at an angle of not more than one hundred thirty-five (135) degrees. If the angle is greater than one hundred thirty-five (135) degrees, the lot shall be considered an "Interior Lot". The setbacks for a front yard shall be met on all abutting streets.

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"


► **Formatted:** Indent: Left: 1.38", No bullets or numbering

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

► **Formatted:** Indent: Left: 1.38", No bullets or numbering

► **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

2.02.186 LOT COVERAGE shall mean the portion of a lot or building site which is occupied by any building or structure, excepting paved areas, walks and swimming pools, regardless of whether said building or structure is intended for human occupancy or not.



Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.187 LOT DEPTH shall mean the horizontal distance between the front and rear lot lines measured in the mean direction of the side lot lines.

2.02.188 LOT, DOUBLE FRONTAGE shall mean a lot having a frontage on two non-intersecting streets as distinguished from a corner lot.

2.02.189 LOT, FRONTAGE shall mean the side of a lot abutting on a legally accessible street right-of-way other than an alley or an improved county road. For the purposes of this definition, on corner lots, all sides of a lot adjacent to streets or roads shall be considered frontage.

2.02.190 LOT, INTERIOR shall mean a lot other than a corner lot.

2.02.191 LOT LINE shall mean the property line bounding a lot.

2.02.192 LOT LINE, FRONT shall mean the property line abutting a street.

2.02.193 LOT LINE, REAR shall mean a lot line not abutting a street which is opposite and most distant from the front lot line.

2.02.194 LOT LINE, SIDE shall mean any lot line *that is* not a front lot line or rear lot line. (*Ordinance No. 1083, 2-17-09*)

2.02.195 LOT, THROUGH shall mean a lot having frontage on two (2) dedicated streets, not including a corner lot.

2.02.196 LOT OF RECORD shall mean a lot held in separate ownership as shown on the records of the County Register of Deeds at the time of the passage of a regulation or regulations establishing the zoning district in which the lot is located.

2.02.197 LOT WIDTH shall mean the average horizontal distance between the side lot lines, measured at right angles to the lot depth at a point midway between the front and rear lot lines.

Section 2.14 - Definitions: M

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Tab stops: Not at 2.75"

Formatted: Tab stops: Not at 2.75"

2.02.198 MAIL ORDER SERVICES shall mean an establishment primarily engaged in the retail sale of products by television, telemarketing, internet, catalog, and mail order. Such a use may include warehousing, shipping, and receiving of merchandise intended for retail sale. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.199 MANUFACTURED HOME A factory-built structure which is to be used as a place for human habitation, which is not constructed or equipped with a permanent hitch or other device allowing it to be moved other than to a permanent site, which does not have permanently attached to its body or frame any wheels or axles, and which bears a label certifying that it was built in compliance with standards promulgated by the United States Department of Housing and Urban Development. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.200 MANUFACTURED HOME PARK shall mean a parcel of land under single ownership that has been planned and improved for the placement of manufactured housing used or to be used for dwelling purposes and where manufactured home spaces are not offered for sale or sold. The term "manufactured home park" does not include sales lots on which new or used manufactured homes are parked for the purposes of storage, inspection, or sale.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.204 MANUFACTURED HOME SUBDIVISION shall mean any area, piece, parcel, tract or plot of ground subdivided and used or intended to be used for the purpose of selling lots for occupancy by manufactured homes.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.202 MANUFACTURING shall mean uses primarily engaged in the mechanical or chemical transformation of materials or substances into new products. These uses are usually described as plants, factories, or mills and characteristically use power driven machines and materials handling equipment. Uses engaged in assembling component parts of manufactured products are also considered manufacturing if the new product is neither a structure nor other fixed improvement. Also included is the blending of material such as lubricating oils, plastics, resins, or liquors. Manufacturing production is usually carried on for the wholesale market, for interplant transfer, or to order for industrial users, rather than for direct sale to the domestic consumer.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.203 MANUFACTURING, LIGHT shall mean an establishment engaged in the indoor manufacturing, assembly, fabrication, packaging or other industrial processing of finished parts or products, primarily from previously prepared materials, or the indoor provision of industrial services, where there are few external effects across property lines. This term includes but is not limited to a business engaged in the processing, fabrication, assembly, treatment, or packaging of food, textile, leather, wood, paper, chemical, plastic, or metal products, but does not include basic industrial processing from raw materials. (Ordinance No. 1053, 1-15-08)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.204 MAP, OFFICIAL ZONING DISTRICT shall mean a map delineating the boundaries of zoning districts which, along with the zoning text, is officially adopted by the La Vista City Council.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.205 MASTER FEE SCHEDULE shall mean a fee schedule maintained by the City of La Vista and passed, and amended periodically, which establishes the required fees to be collected for specific Planning, Zoning, Subdivision, and Building Inspection activities.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.206 MECHANICAL EQUIPMENT shall mean equipment, devices, and accessories, the use of which relates to water supply, drainage, heating, ventilating, air conditioning, and similar purposes.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.207 MEDICAL / DENTAL OFFICES / CLINICS shall mean a building or portion of a building containing offices and facilities for providing medical, dental, and psychiatric services for outpatients only. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.208 MEETING HALL shall mean a building designed for public assembly. (Ordinance No. 1083, 2-17-09)

2.02.209 MICROBREWERY (see Brew Pub) (Ordinance No. 1083, 2-17-09)

2.02.210 MINI-STORAGE OR MINI-WAREHOUSE (See Self-Service Storage Facility)

2.02.211 MISCELLANEOUS REPAIR SERVICES shall include electrical repair shops; watch, clock and jewelry repair shops; and re-upholstery and furniture repair. (See also Standard Industrial Classification (SIC) Major Group 76, published by the U.S. Department of Labor) (Ordinance No. 1053, 1-15-08)

2.02.212 MISCELLANEOUS STRUCTURES shall mean structures, other than buildings, visible from public ways. Examples are: memorials, antennas, water tanks and towers, sheds, shelters, fences, and walls, kennels, transformers, drive-up facilities. (Ordinance No. 1083, 2-17-09)

2.02.213 MIXED USE shall mean properties where various uses, such as office, commercial, institutional, and residential, are combined in a single building or on a single site in an integrated development project with significant functional interrelationships and a coherent physical design.

2.02.214 MOBILE HOME (See Dwelling, Mobile Home)

2.02.215 MOBILE HOME PARK (See Manufactured Home Park)

2.02.216 MOBILE HOME SUBDIVISION (See Manufactured Home Subdivision)

2.02.217 MORTUARY shall mean an establishment in which the deceased are prepared for burial or cremation. The facility may include funeral services and spaces for informal gatherings or display of funeral equipment. This classification excludes cemeteries. (Ordinance No. 1083, 2-17-09)

2.02.218 MOTEL (See Hotel)

2.02.219 MOTOR VEHICLE shall mean every self-propelled vehicle, not operated upon rails, except mopeds and self-propelled invalid chairs. (Ordinance No. 891, 2-04-03)

Section 2.15 - Definitions: N

2.02.220 NEWSSTAND shall mean a temporary structure manned by a vendor, whom sells newspapers, magazines and other periodicals. (Ordinance No. 1083, 2-17-09)

2.02.221 NON-CONFORMING STRUCTURE shall mean a building or portion thereof which was lawful when established but which does not conform to subsequently established zoning or zoning regulations. (Ordinance No. 1083, 2-17-09)

2.02.222 NON-CONFORMING USE shall mean a use lawful when established but which does not conform to subsequently established zoning or zoning regulations.

2.02.223 NUISANCE shall mean anything that interferes with the use or enjoyment of property, endangers personal health or safety, or is offensive to the senses such as noise, dust, odor, smoke, gas, pollution, congestion, lighting, and litter.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.224 NURSERY shall mean the use of a premises for the propagation, cultivation, and growth of trees, shrubs, plants, vines, and the like from seed or stock, and the sale thereof, and including the sale of trees, shrubs, plants, vines, and the like purchased elsewhere and transplanted into the soil of the premises. In connection with the sale of plants, such fungicides, insecticides, chemicals, peat moss, humus, mulches, and fertilizers as are intended to be used in preserving the life and health of the plants may be sold.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.225 NURSING CARE AND REHABILITATION FACILITIES shall mean a type of care facility for persons with chronic illness or disability, particularly older people who have mobility and eating problems. These facilities are licensed by the State of Nebraska and offer 24-hour room and board and health care services, including basic and skilled nursing care, rehabilitation, hospice, and a full range of other therapies, treatments, and programs.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Section 2.16 - Definitions: O

2.02.226 OFFICE shall mean a building or a portion of a building wherein services are performed involving, primarily, administrative, professional, or clerical operations.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Font: Not Italic

2.02.227 OFFICE PARK shall mean a development which contains two or more separate office buildings, accessory and supporting uses, and open space all designed, planned, constructed, and maintained on a coordinated basis. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.228 OPEN SPACE shall mean a parcel or parcels of land, together with the improvements thereon, primarily set aside for recreational use and enjoyment, exclusive of land areas used for streets, alleys, roads, driveways, parking areas, structures, and buildings.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.229 OPEN SPACE, COMMON shall mean a separate and distinct area set aside as open space within or related to a development, and not on individually owned lots or dedicated for public use, but which is designed and intended for the common use or enjoyment of the residents of the development. Rights-of-way, private streets, driveways, parking lots or other surfaces designed or intended for vehicular use or required yards shall not be included as common open space.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.230 OUTLOT shall mean a lot remnant or parcel of land left over after platting, which is intended as open space or other use, for which no building permit shall be issued on any private structures.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.231 OUTDOOR STORAGE shall mean the storage of any material for a period greater than 72 hours not in an enclosed building, including items for sale, lease, processing, and repair (including motor vehicles). (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.232 OVERLAY DISTRICT shall mean a district in which additional requirements act in conjunction with the underlying zoning district. The underlying zoning district designation does not change. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.233 OWNER shall mean one (1) or more persons, including corporations, who have title to the property, building or structure in question.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Section 2.17 - Definitions: P

2.02.234 PARCEL shall mean a lot or a contiguous group of lots in single ownership or under single control, which may be considered as a unit for purposes of development.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

common ownership, contiguous, and used as a single tract (*See also, Parcel*)
(*Ordinance No. 1083, 2-17-09*)

2.02.254 PRESCHOOL shall mean a school or center for children under school age, whether licensed as a day care center or not, shall be approved by the Nebraska State Fire Marshall as being in safety conformance with the National Fire Protection Association, Pamphlet 101, known as the Life Safety Code and shall be approved by the Nebraska Department of Health and Welfare as meeting their health and welfare standards. (*Ordinance No. 1083, 2-17-09*)

2.02.252 PRINCIPAL BUILDING shall mean a building within which the main or primary use of the lot or premises is located. (*See also Use, Principal*) (*Ordinance No. 1083, 2-17-09*)

2.02.253 PUBLIC FACILITIES shall mean any building held, used, or controlled exclusively for public purposes by any department or branch of federal, state, county, or city government. A building belonging to or used by the public for the transaction of public or quasi-public business. Public services may be rendered from such facilities. (*Ordinance No. 1083, 2-17-09*)

2.02.254 PUBLIC SERVICES shall mean services provided by a public agency within a government facility for purposes of public safety and emergency services, including a facility that provides police or fire protection and related administrative facilities. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 0", First line: 0",
Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or
numbering

Formatted: Indent: Left: 0", First line: 0",
Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or
numbering

Formatted: Indent: Left: 0", First line: 0",
Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or
numbering

Formatted: Indent: Left: 0", First line: 0",
Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or
numbering

Section 2.18 – Definitions: Q

Section 2.19 - Definitions: R

2.02.255 RECREATIONAL ESTABLISHMENT (*see Recreational Facility*)
(*Ordinance No. 891, 2-04-03*)

2.02.256 RECREATIONAL FACILITY shall mean *public or private* facilities for the use of passive and active recreation including tennis, handball, racquetball, basketball, track and field, jogging, baseball, soccer, skating, swimming, or golf. This shall include country clubs and athletic clubs, but not facilities accessory to a private residence used only by the owner and guests, nor arenas or stadiums used primarily for spectators to watch athletic events. In addition, recreational facilities shall mean museums, amphitheaters, race tracks (including all motor powered vehicles) and wildlife conservation areas (used for public viewing), and theme parks. (*Ordinance No. 891, 2-04-03*)

Formatted: Indent: Left: 0", First line: 0",
Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or
numbering

Formatted: Indent: Left: 0", First line: 0",
Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or
numbering

2.02.257 RECREATIONAL VEHICLE (RV) shall mean a vehicular unit less than forty (40) feet in overall length, eight (8) feet in width, or twelve (12) feet in overall height, primarily designed as a temporary living quarters for recreational camping or travel use having either its own power or designed to be mounted on or drawn by a motor vehicle. Recreational vehicle includes motor home, truck camper, travel trailer, camping trailer, and fifth wheel.

Formatted: Indent: Left: 0", First line: 0",
Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or
numbering

2.02.258 RESIDENCE shall mean a building used, designed, or intended to be used as a home or dwelling place for one (1) or more families.

Formatted: Indent: Left: 0", First line: 0",
Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or
numbering

2.02.259 RESERVATION CENTER shall mean a travel agency; or other such agency involved in selling and arranging transportation, tours, trips, and accommodations for tourists. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 0", First line: 0",
Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or
numbering

2.02.260 RESTAURANT shall mean a public eating establishment at which the primary function is the preparation and serving of food primarily to persons seated within the building.

Formatted: Indent: Left: 0", First line: 0",
Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or
numbering

Section 2.20 - Definitions: S

2.02.261 **RESTAURANT, FAST FOOD** shall mean an establishment whose principal business is the sale of food and/or beverages in ready-to-consume individual servings, for consumption either within the establishment, for carryout, *drive-thru*, or drive-in; and where food and/or beverages are usually served in paper, plastic, or other disposable containers. *(Ordinance No. 1083, 2-17-09)*

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.262 **RETAIL TRADE** shall mean uses primarily engaged in selling merchandise for personal or household consumption and rendering services incidental to the sale of goods. Uses engaged in retail trade sell merchandise to the general public or to households for personal consumption.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.263 **REZONING** shall mean an amendment to or change to the *Official Zoning District Map*. *(Ordinance No. 1083, 2-17-09)*

Formatted: Tab stops: Not at 0.5"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.264 **RIGHT-OF-WAY** shall mean an area or strip of land, either public or private, on which an irrevocable right of passage has been dedicated, recorded, or otherwise legally established for the use of vehicles or pedestrians or both.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.265 **ROAD, PRIVATE** shall mean a way, other than driveways, open to vehicular ingress and egress established for the benefit of certain, adjacent properties.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.266 **ROAD, PUBLIC** shall mean all public right-of-way reserved or dedicated for *utilities and vehicular and pedestrian traffic*. *(Ordinance No. 1083, 2-17-09)*

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.267 **SATELLITE DISH ANTENNA** shall mean a round, parabolic antenna incorporating a reflective surface that is solid, open mesh, or bar configured and is in the shape of a shallow dish, or cone and used to transmit and/or receive radio or electromagnetic waves.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.268 **SCREENING** shall mean a structure *or* planting that conceals from view from public ways the area behind such structure or planting.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.269 **SELF-SERVICE STORAGE FACILITY** shall mean a building or group of buildings containing individual, compartmentalized, and controlled access stalls or lockers for storage.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.270 **SERVICE STATIONS** shall mean buildings and premises where the primary use is the supply and dispensing at retail of motor fuels, lubricants, batteries, tires, and motor vehicle accessories and where light maintenance activities such as engine tune-ups, lubrications, and washing may be conducted, but not including heavy maintenance and repair such as engine overhauls, painting, and body repair.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.274 **SETBACK, FRONT YARD** shall mean the line which defines the depth of the required front yard. Said setback line shall be parallel with the right-of-way line *or other access way*. *(Ordinance No. 1083, 2-17-09)*

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.272 **SETBACK, REAR YARD OR SIDE YARD** shall mean the line which defines the width or depth of the required rear or side yard. Said setback line shall be parallel with the property line, *offset* by the perpendicular distance prescribed for the yard in the district. *(Ordinance No. 1083, 2-17-09)*

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.273 **SHOPPING CENTER** shall mean a group of commercial establishments planned, constructed, and managed as a total entity with customer and employee parking provided on-site, provisions for goods delivery that is separated from customer access, aesthetic considerations, and protection from the elements.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.274 SHOPPING CENTER, COMMERCIAL STRIP shall mean a commercial development, usually one store deep, that fronts on a major street for a distance of one city block or more. Includes individual buildings on their own lots, with or without on-site parking and small linear shopping centers with shallow on-site parking in front of the stores.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.275 SHOPPING CENTER, OUTLET shall mean a commercial development that consists mostly of manufacturers' outlet stores selling their own brands at a discounted price. This definition includes all forms of centers, such as strip style, enclosed mall style, and village clustered style centers.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.02.276 SIGHT TRIANGLE is an area at a street intersection in which nothing shall be erected, placed, planted, or allowed to grow in such a manner as to materially impede vision between a height of two-and-a-half (2 1/2) feet and ten (10) feet above the

grades of the bottom of the curb of the intersecting streets, measured from the point of intersection of the centerline of the streets, sixty (60) feet in each direction along the centerline of the streets. At the intersection of major or *other* arterial streets, the sixty (60) foot distance shall be increased to ninety (90) feet for each arterial leg of the intersection. (*Ordinance No. 891, 2-04-03*)

2.07.277 SIGN shall mean and include any outdoor display, declaration, device, figure, drawing, illustration, message, placard, poster, billboard, insignia, or other things which are designed, intended, or used for direction, information, identification, or to advertise, to inform, or to promote any business, product activity, service, or any interest, except the following:

Signs less than fifty (50) square feet in area and less than twenty-five (25) feet in height of a public or quasi-public nature or other official notices that are authorized by the State of Nebraska, City of La Vista, or a Federal Government Agency, directional, informational, or other official signs or notices authorized by law.

Comment [AB1]: Diagram is above with another definition.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 0.25", No bullets or numbering

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0.75"

2.07.278 SIGN, ANIMATED shall mean any sign that uses movement or change of lighting to depict action or create a special effect or scene.

Formatted: Indent: Left: 0", First line: 0"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.279 SIGN AREA shall refer to that portion of a sign on which copy can be placed but not including the minimal supporting framework or bracing. The area of individually painted letter signs, individual letter signs or directly or indirectly illuminated individual letter signs, shall be calculated on the basis of the smallest geometric figure that will enclose the entire copy area of the sign. Any such calculation shall include the areas between the letters and lines, as well as the areas of any devices, illuminated or non-illuminated. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 0", First line: 0"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.280 SIGN, AUDIBLE shall mean any sign that conveys either a written message supported by an audible noise including music, spoken message, and / or sounds to attract attention to the sign. Audible signs also include signs conveying only the audible noise including music, spoken message, and / or sounds to attract attention.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.284 SIGN, BANNER shall mean any sign of lightweight fabric or similar material that is permanently mounted to a pole or building by a permanent frame at one or more edges. National flags, state or municipal flags, or official flag of any institution or business shall not be considered banners. Banner signs shall not represent a commercial message.



Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering


2.07.282 SIGN, BILLBOARD shall mean a sign that identifies or communicates a commercial or noncommercial message related to an activity conducted, a service rendered, or a commodity sold at a location other than where the sign is located.



Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.283 SIGN, BUILDING MARKER shall mean any sign indicating the name of a building and date and incidental information about its construction, which sign is cut into a masonry surface or made of bronze or other permanent material.



Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.284 SIGN, CANOPY shall mean any sign that is a part of or attached to an awning, canopy, or other fabric, plastic, or structural protective cover over a door, entrance, window, or outdoor service area. A marquee is not a canopy. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.285 SIGN, CENTER IDENTIFICATION shall mean any sign erected to provide direction to a development including multiple uses and / or structures within the development. Center Identification signs shall include the name of said development and may include the names of major tenants of the development. Center Identification Signs shall typically be similar to Ground (Monument) signs. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"


Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.286 SIGN, CONSTRUCTION shall mean a temporary sign identifying an architect, engineer, contractor, subcontractor, and/or building material supplier who participates in construction on the property on which the sign is located. (*Ordinance No. 871, 10-15-02*); (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.287 SIGN, ELECTRONIC MESSAGE BOARD shall mean any sign capable of displaying words, symbols, figures, or images that can be electronically or mechanically changed by remote or automatic means. (*Ordinance No. 1144, 5-17-11*)



Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Sign, Monument
Sign, Electronic Message
Sign, Flashing

2.07.288 SIGN, FLASHING shall mean a sign, which, by method or manner of illumination, flashes on or off, winks, or blinks with varying light intensity, shows motion, or creates the illusion of being on or off.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.289 SIGN, FREESTANDING shall mean any sign supported by uprights or braces placed on or in the ground, which is used principally for advertising or identification purposes and is not supported by any building.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.290 SIGN, IDENTIFICATION shall mean a sign giving the nature, logo, trademark, or other identifying symbol; address; or any combination of the name, symbol, and address of a building, business, development, or establishment on the premises where it is located.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.291 SIGN, ILLUMINATED shall mean a sign illuminated in any manner by an artificial light source.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.292 SIGN, INCIDENTAL shall mean a sign, generally informational, that has a purpose secondary to the use of the zone lot on which it is located, such as "no parking," "entrance," "loading only," "telephone," and other similar directives. No sign with a commercial message legible from a position off the zone lot on which the sign is located shall be considered incidental. Incidental signs may be attached or painted on the wall, or they may be freestanding signs. (*Ordinance No. 1083, 2-17-09*)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.293 SIGN, MARQUEE shall mean any permanent roof-like structure projecting beyond a building or extending along and projecting beyond the wall of the building, generally designed and constructed to provide protection from the weather.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

2.07.294 SIGN, MONUMENT shall mean a sign mounted directly to the ground with a maximum height not to exceed ten (10) feet.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.295 SIGN, NAMEPLATE shall mean a sign not exceeding two (2) square feet for each dwelling.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.296 SIGN, NONCONFORMING shall mean any sign that does not conform to the requirements of this ordinance

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.297 SIGN, OFF-PREMISES shall mean a sign including the supporting sign structure which directs the attention of the general public to a business, service, or activity not usually conducted, or a product not offered or sold, upon the premises where such sign is located.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.298 SIGN, ON-PREMISE shall mean a sign, display, or device-advertising activities conducted on the property on which such sign is located.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.299 SIGN, PENNANT shall mean any lightweight plastic, fabric, or other material, whether or not containing a message of any kind, suspended from a rope, wire, or string, usually in series, designed to move in the wind.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.300 SIGN, POLE shall mean a sign that is mounted on a freestanding pole or other support so that the bottom edge of the sign face is six (6) feet or more above grade.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering



2.07.304 SIGN, PORTABLE shall mean a sign, usually of a temporary nature, not securely anchored to the ground or to a building or structure and which obtains some or all of its structural stability with respect to wind or other normally applied forces by means of its geometry or character. Examples are: menu and sandwich board signs, balloons used as signs, umbrellas used for advertising, and signs attached to or painted on vehicles parked and visible from the public right-of-way, unless said vehicle is used in the normal day-to-day operations (deliveries and transportation of personnel) of the business. This definition also includes any and all sandwich boards supported by human beings or animals.

Formatted: Indent: Left: 1.38", No bullets or numbering



Sign, Projecting

2.07.302 SIGN, PROJECT DIRECTORY shall mean a sign fronting on a road containing only the name of the principal use and directional arrow to the principal use. Project directory signs are intended to direct attention to planned multi-tenant developments which are not easily accessible off of such roads and where on-premise signage for that development (or any tenants within the development) would not otherwise be visible by the motorists traveling on nearby arterial or collector roads at the closest point of access. *(Ordinance No. 1144, 5-17-11)*

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.303 SIGN, PROJECTING shall mean a projecting sign attached to a building in such a manner that its leading edge extends more than eight (8) inches beyond the surface of such building or wall.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.304 SIGN, REAL ESTATE shall mean a temporary sign that identifies property or properties that are for sale or lease.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.305 SIGN, ROOF shall mean a sign identifying the name of a business, enterprise, or the product sold on the premises and erected on or over the roof of a building. *(Ordinance No. 1083, 2-17-09)*

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.306 SIGN SETBACK shall mean the horizontal distance from the property line to the nearest projection of the existing or proposed sign.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.307 SIGN, SUBDIVISION shall mean a sign erected on a subdivision which identifies the platted subdivision where the sign is located.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.308 SIGN SURFACE shall mean the entire area of a sign.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.309 SIGN, SUSPENDED shall mean a sign that is suspended from the underside of a horizontal plane surface and is supported by such surface.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.310 SIGN, TEMPORARY shall mean a sign constructed of cloth, fabric, or other material with or without a structural frame intended for a limited period of display, including displays for holidays or public demonstrations. Temporary signs shall include portable signs as defined in this section.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.314 SIGN, VIDEO shall mean any on-premises or off-premises sign that conveys either a commercial or non-commercial message, including a business or organization name, through means of a television or other video screen. *This definition shall include electronic message board signs. (Ordinance No. 1083, 2-17-09)*

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering


Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 0.5"

Formatted: Indent: Left: 1.38", No bullets or numbering



Sign, Subdivision

2.07.312 SIGN, WALL shall mean any sign attached parallel to, but within eight inches of, a wall, painted on the wall surface of, or erected and confined within the limits of an outside wall of any building or structure, which is supported by such wall or building, and which displays only one sign surface.



Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.313 SIGN, WINDOW shall mean any sign, pictures, symbol, or combination thereof, designed to communicate information about an activity, business, commodity, event, sale, or service, that is placed inside a window or upon the window panes or glass and is visible from the exterior of the window.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.314 SIGN BASE shall mean any decorative, functional element extending upward from grade to the start of the sign.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.315 SIMILAR USE shall mean the use of land, buildings, or structures of like kind or general nature with other uses within a zoning district as related to bulk, intensity of use, traffic generation and congestion, function, public services requirements, aesthetics or other similarities.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.316 SITE PLAN shall mean a plan, prepared to scale, showing accurately and with complete dimensioning, the boundaries of a site and the location of all buildings, structures, uses, drives, parking, drainage, landscape features, and other principal site development improvements for a specific parcel of land.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.317 SOCIAL CLUB OR FRATERNAL ORGANIZATIONS shall mean an association of persons (whether or not incorporated), religious or otherwise, for a common purpose, but not including groups which are organized primarily to render a service carried on as a business for profit. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.318 SOLID WASTE shall mean waste materials consisting of garbage, trash, refuse, rubble, sewage, offal, dead animals, or paunch manure.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.319 SPECIAL or VOCATIONAL TRAINING FACILITIES shall mean a specialized instructional establishment that provides on-site training of business, commercial, and/or trade skills such as accounting, data processing, and computer repair. This classification excludes establishments providing training in an activity that is not otherwise permitted in the zone. Incidental instructional services in conjunction with another primary use shall not be included in this definition. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.320 SPECIFIED ANATOMICAL AREAS shall mean anatomical areas consisting of:

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"
Formatted: Indent: Left: 1.38", No bullets or numbering

Less than completely and opaquely covered human genitals, pubic region, buttock, anus, or female breast(s) below a point immediately above the top of the areola; and,

Formatted: Indent: Left: 0.75"

Human male genitals in a discernibly turgid state, even if completely and opaquely covered.

2.07.324 SPECIFIED SEXUAL ACTIVITIES shall mean activities consisting of the following:

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 1.5"
Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.321.01 Actual or simulated sexual intercourse, oral copulation, anal intercourse, oral-anal copulation, bestiality, direct physical stimulation of unclothed genitals, flagellation or torture in the context of a sexual relationship, or the use of excretory functions in the context of a sexual relationship, and any of the following sexually-oriented acts of conduct: Anilingus, buggery,

Formatted: Indent: Left: 1.75", No bullets or numbering

coprophagy, coprophilia, cunnilingus, fellatio, necrophilia, pederasty, pedophilia, piquerism, sapphism, zoerasty; or

2.07.321.02 Clearly depicted human genitals in the state of sexual stimulation, arousal, or tumescent; or

2.07.321.03 Use of human or animal ejaculation, sodomy, oral copulation, coitus, or masturbation; or

2.07.321.04 Fondling or touching of nude human genitals, pubic region, buttocks, or female breast(s); or

2.07.321.05 Situation involving a person or persons, any of whom are nude, clad in undergarments or in sexually revealing costumes, and who are engaged in activities involving the flagellation, torture, flogging, binding, or other physical restraint or any such persons; or

2.07.321.06 Erotic or lewd touching, fondling, or other sexually-oriented contact with an animal by a human being; or

2.07.321.07 Human excretion, urination, menstruation, vaginal, or anal irrigation.

2.07.322 STATE shall mean the State of Nebraska.

2.07.323 STORAGE shall mean the keeping, in a roofed or unroofed area, of any goods, junk, material, merchandise, or vehicles on the same tract or premises for more than thirty (30) days.

2.07.324 STORY shall mean a space in a building between the surface of any floor and the surface of the floor above, or if there is not floor above, then the space between such floor and the ceiling or roof above.

2.07.325 STREET shall mean a public thoroughfare or right-of-way dedicated, deeded, or condemned for use as such, other than an alley, which affords the principal means of access to abutting property including avenue, place, way, drive, lane, boulevard, highway, road and any other thoroughfare except as excluded in this Regulation.

2.07.326 STREET, ARTERIAL shall mean a street designed with the primary function of efficient movement of through traffic between and around areas of a City, City, or county with controlled access to abutting property.

2.07.327 STREET, COLLECTOR shall mean a street or highway, which is intended to carry traffic from a minor street to major streets. Collector streets are usually the principal entrance streets to residential developments and the streets for circulation within the development.

2.07.328 STREET FRONTRAGE shall mean the distance for which a lot line of a zone lot adjoins a public street, from one lot line intersecting said street to the furthest distant lot line intersecting the same street.

2.07.329 STREET, LOCAL shall mean a street designed for local traffic that provides direct access to abutting residential, commercial, or industrial properties.

2.07.330 STREET, PRIVATE shall mean an open, unoccupied space, other than a street or alley dedicated to the public, but permanently established as the principal means of vehicular access to abutting properties. (*Ordinance No. 1083, 2-17-09*)

2.07.331 STREETSCAPE shall mean the scene as may be observed along a street right-of-way composed of natural and man-made components, including buildings, paving, plantings, poles, signs, benches, and other miscellaneous amenities. (*Ordinance No. 1083, 2-17-09*)

Comment [AB2]: Again, some sub-numbering is needed.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 1.5"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

2.07.332 STRUCTURE shall mean anything constructed or built, any edifice or building of any kind, or any piece of work artificially built up or composed of parts joined together in some definite manner, which requires location on the ground or is attached to something having a location on the ground, including swimming and wading pools and covered patios, excepting outdoor areas such as paved areas, walks, tennis courts, and similar recreation areas.

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.333 STRUCTURE, TEMPORARY shall mean a structure permitted as a temporary use. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

2.07.334 STRUCTURAL ALTERATION shall mean any change in the support members of a building, such as in a bearing wall, column, beam or girder, floor or ceiling joists, roof rafters, roof diaphragms, foundations, piles, or retaining walls or similar components.

2.07.335 SUBDIVISION shall mean the division of land, lot, tract, or parcel into two or more lots, parcels, plats, or sites, or other divisions of land for the purpose of sale, lease, offer, or development, whether immediate or future. (Ordinance No. 1083, 2-17-09)

Section 2.21 - Definitions: T

2.07.336 TANNING SPA or SALON shall mean any business that uses artificial lighting or other systems to produce a tan on an individual's body. These facilities may be either a stand-alone business or as an accessory use in spas, gymnasiums, athletic clubs, health clubs, and styling salons. This use is not included with any type of adult establishment. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.337 TAVERN AND COCKTAIL LOUNGE shall mean any establishment whose principal business is serving alcoholic beverages at retail for consumption on the premises. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.338 TELECOMMUNICATIONS FACILITY shall mean any facility that transmits and/or receives signals by electromagnetic or optical means, including antennas, microwave dishes, horns, or similar types of equipment, towers or similar structures supporting such equipment, and equipment buildings. (Ordinance No. 1083, 2-17-09)

2.07.339 TELEPHONE EXCHANGE shall mean a building used exclusively for the transmission and exchange of telephone messages, but the term shall not include wireless communication towers. (Ordinance No. 1083, 2-17-09)

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

2.07.340 TEMPORARY USE shall mean a use intended for limited duration, *not to exceed six (6) months*, to be located in a zoning district not permitting such use. (Ordinance No. 1083, 2-17-09)

2.07.341 THEATER shall mean a building or structure used for dramatic, operatic, motion pictures, or other performance, for admission to which entrance money is received and no audience participation or meal service.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

2.07.342 TOWER shall mean a structure situated on a site that is intended for transmitting or receiving television, radio, or telephone communications. (Also, see Antenna)

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.07.343 TOWNHOUSE shall mean a one-family dwelling unit, with a private entrance, which is part of a structure whose dwelling units are attached horizontally in a linear arrangement, and having a totally exposed front and rear wall to be used for access, light, and ventilation.

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.07.344 TRANSPORTATION SERVICES shall mean establishments providing services incidental to transportation, such as forwarding, packing, crating, or other means of preparing goods for shipping. (See also Standard Industrial Classification (SIC) Industry Group 473 and description 4783, published by the U.S. Department of Labor.) (Ordinance No. 1053, 1-15-08)

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

Section 2.22 - Definitions: U

2.07.345 USE, PRINCIPAL shall mean the main use of land or structure, as distinguished from an accessory use. (Also, see Principal Building)

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.07.346 UTILITARIAN STRUCTURE shall mean a structure or enclosure relating to mechanical or electrical services to a building or development.

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.07.347 UTILITY HARDWARE shall mean devices such as poles, crossarms, transformers and vaults, gas pressure regulating assemblies, hydrants, and buffalo boxes that are used for water, gas, oil, sewer, and electrical services to a building or a project.

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.07.348 UTILITY SERVICE shall mean any device, including wire, pipe, and conduit, which carries gas, water, electricity, oil and communications into a building or development.

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

Section 2.23 - Definitions: V

2.07.349 VARIANCE shall mean a relief granted by the Board of Adjustment from or variation of the provisions of this Ordinance, other than use regulations, as applied to a specific piece of property, as distinct from rezoning. (Ordinance No. 1083, 2-17-09)

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.07.350 VETERINARY SERVICES shall mean a building or part of a building used for the care, diagnosis, and treatment of sick, ailing, infirm, or injured animals, and those who are in need of medical or surgical attention. Such clinics may or may not also provide long-term lodging for ill or unwanted animals, or lodging for healthy animals on a fee basis. Such clinics may or may not also provide general grooming practices for such animals. (Ordinance No. 871, 10-15-02)

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

Section 2.24 – Definitions: W

2.07.354 WAREHOUSE shall mean a building used primarily for the storage of goods and materials.

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

2.07.352 WHOLESALE TRADE shall mean a use primarily engaged in selling merchandise to retailers; to industrial, commercial, institutional, farm or professional business users; or to other wholesalers; or acting as agents or brokers in buying merchandise for or selling merchandise to such persons or companies. The principal types of establishments included are: Merchant wholesalers; sales branches and sales offices (but not retail stores) maintained by manufacturing enterprises apart from their plants for the purpose of marketing their products; agents, merchandise or commodity

← **Formatted:** Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

← **Formatted:** Indent: Left: 1.38", No bullets or numbering

brokers, and commission merchants; petroleum bulk storage, assemblers, buyers, and associations engaged in cooperative marketing of farm products. The chief functions of uses in wholesale trade are selling goods to trading establishments, or to industrial, commercial, institutional, farm and professional; and bringing buyer and seller together. In addition to selling, functions frequently performed by wholesale establishments include maintaining inventories of goods; extending credit; physically assembling, sorting and grading goods in large lots, breaking bulk and redistribution in smaller lots; delivery; refrigeration; and various types of promotion such as advertising and label designing.


2.07.353 WIND ENERGY SYSTEM or WIND ENERGY CONVERSION SYSTEM (WECS) shall mean a wind-driven machine that converts wind energy into electrical power for the primary purpose of on-site use or resale for off-site use. (Ordinance No. 1083, 2-17-09)

2.07.354 WIRELESS COMMUNICATIONS TOWER shall mean a structure designed and constructed to support one or more antennas used by commercial wireless telecommunication facilities and including all appurtenant devices attached to it. A tower can be freestanding (solely self-supported by attachment to the ground) or supported (attached directly to the ground and with guy wires), of either lattice or monopole construction. (Ordinance No. 1083, 2-17-09)

Section 2.25 – Definitions: X

Section 2.26 - Definitions: Y

2.07.355 YARD shall mean any open space on the same lot with a building or a dwelling group, which open space is unoccupied and unobstructed from the ground upward to the sky, except for building projections or for accessory buildings or structures permitted by this Regulation.



3

2.07.356 YARD, FRONT shall mean a space between the front yard setback line and the front lot line or *right-of-way line*, and extending the full width of the lot. (Ordinance No. 1083, 2-17-09)

2.07.357 YARD, REAR shall mean a space between the rear yard setback line and the rear lot line, extending the full width of the lot.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 0.25", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

2.07.358 YARD, SIDE shall mean a space extending from the front yard or from the front lot line where no front yard is required by this Regulation, to the rear yard, or rear lot line, between a side lot line and the side yard setback line.

Formatted: Indent: Left: 1.38", No bullets or numbering

Section 2.27 - Definitions: Z

2.07.359 ZONE LOT shall mean a parcel of land in single ownership that is of sufficient size to meet minimum zoning requirements for area, coverage, and use, and that can provide such yards and other open spaces as required by the zoning regulations.

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 0", First line: 0", Tab stops: Not at 2.75"

Formatted: Indent: Left: 1.38", No bullets or numbering

